



राक्सिराङ्ग गाउँपालिका

स्थानीय राजपत्र

खण्ड ०८, संख्या ४, मकवानपुर, श्रावण ३० गते, २०८१ साल

भाग २

राक्सिराङ्ग गाउँपालिका

स्थानीय सरकार संचालन ऐन २०७४ को दफा १०२ को उपदफा (२)

बमोजिम राक्सिराङ्ग गाउँ कार्यापालिकाले बनाएको तल लेखिए

बमोजिमको दररेट तथा दर विश्लेषण सोही दफाको उपदफा (३)

बमोजिम सर्व साधारणको जानकारीको लागि

प्रकाशित गरिएको छ ।

राक्सिराङ्ग गाउँपालिकाको आ.व. २०८१/०८२ को दररेट तथा दर
विश्लेषण , २०८१

संवत् २०८१ सालको दररेट तथा दर विश्लेषण नं. १०६

खण्ड ०८, संख्या ०४, मकवानपुर, श्रावण ३० गते, २०८१ साल

राक्सिराङ्ग गाउँपालिकाको आ.व. २०८१/०८२ को दररेट तथा दर
विश्लेषण , २०८१

Summary of Rates For Contractor

SN	Acti vity No.	SS Cla use	Description	Unit	Contractor Rate	Remarks
<u>1. Site Clearance</u>						
1	2.1	201	Clearing and grubbing road land including uprooting rank vegetation, grass, bushes, shrubs, saplings and trees girth up to 300 mm, removal of stumps of trees cut earlier and disposal of unserviceable materials and stacking of serviceable Material to be used or auctioned, up to a lead of 30 meters including removal and disposal of top organic soil not exceeding 150 mm in thickness. By Mechanical Means In area of light jungle (less than 15 number per 100 sqm, Unit = sqm, (for 10,000 sqm))	Sqm	5.22	
2	2.2	201	Cutting of Trees, including cutting of Trunks, Branches and Removal Cutting of trees, including cutting of trunks, branches and	no.	1081.91	

Summary of Rates For Contractor

SN	Acti vity No.	SS Cla use	Description	Unit	Contractor Rate	Remarks
			removal of stumps, roots, stacking of serviceable Material with all lifts and up to a lead of 1000 meters and earth filling in the depression/pit. Unit = Number (for 30 number) (i) Girth from 300 mm to 900 mm			
<u>2. Pipe Drains</u>						
1	7.1 A	701	Providing, Jointing and Laying HDPE Pipes with or without collar etc. complete in place as per Drawing and Technical Specifications (Size 110mm/125 mm outer dia.)	Rm	706.25	
2	7.2 A	701	Providing and Laying RCC 300mm dia NP3 Flush jointed pipe for culvert including fixing with cement mortar 1:2 as per drawing and technical specifications	Rm	4375.75	
3	7.2 B	701	Providing and Laying RCC 450mm dia NP3 Flush jointed pipe for culvert including fixing with cement mortar 1:2 as per drawing and technical specifications	Rm	6228.64	

Summary of Rates For Contractor

SN	Acti vity No.	SS Cla use	Description	Unit	Contractor Rate	Remarks
4	7.2. C	701	Providing and Laying RCC 600mm dia NP3 Flush jointed pipe for culvert including fixing with cement mortar 1:2 as per drawing and technical specifications	Rm	8458.74	
5	7.2 D	701	Providing and Laying RCC 900mm dia NP3 Flush jointed pipe for culvert including fixing with cement mortar 1:2 as per drawing and technical specifications	Rm	11442.43	

3. Earth Works In Excavation

1	9.1.I .B	905	Roadway excavation in all types of soil as per Drawing and Technical Specification including removal of stumps and other deleterious matter, all lift and leads as per Drawing and Instruction of the Engineer.	Cum	76.35	
2	9.1.I .B	905	Roadway excavation in ordinary rock as per Drawing and Technical Specification including all lift and leads as per Drawing and Instruction of the Engineer. (Mechanical Means)	Cum	229.07	

Summary of Rates For Contractor

SN	Acti vity No.	SS Cla use	Description	Unit	Contractor Rate	Remarks
3	9.1.I V.A	905	Roadway excavation in hard rock with rock breakers including breaking rock lift and lead for disposal as per Drawing and Technical Specification. (Mechanical Means)	Cum	1477.47	
4	9.4.I .B.i	907	Earthwork in excavation of foundation of structure in ordinary soil including construction of shoring and bracing, removal of stumps and other deleterious matter and backfilling with approved material as drawings and technical specifications.@ Depth upto 3m (mechanical means)	Cum	114.53	
5	9.4.I .B.ii	907	Earthwork in excavation of foundation of structure in ordinary soil including construction of shoring and bracing, removal of stumps and other deleterious matter and backfilling with approved material as drawings and technical specifications.@ Depth	Cum	130.89	

Summary of Rates For Contractor

SN	Acti vity No.	SS Cla use	Description	Unit	Contractor Rate	Remarks
			3 to 6m (mechanical means)			
6	9.4.I .B.iii	907	Earthwork in excavation of foundation of structure in ordinary soil including construction of shoring and bracing, removal of stumps and other deleterius matter and backfilling with approved material as drawings and technical specifications.@ Depth above 6m (mechanical means)	Cum	165.90	
7	9.4.I I.B.	907	Earthwork in excavation of foundation of structure in ordinary Rock including construction of shoring and bracing, removal of stumps and other deleterius matter and backfilling with approved material as drawings and technical specifications.@ Depth Up to 3m (mechanical means)	Cum	305.43	

खण्ड ०८, संख्या ०४, मकवानपुर, श्रावण ३० गते, २०८१ साल

Summary of Rates For Contractor

SN	Acti vity No.	SS Cla use	Description	Unit	Contractor Rate	Remarks
8	9.4.I V.A.	907	Earthwork in excavation of foundation of structure in Hard Rock including construction of shoring and bracing, removal of stumps and other deleterius matter and backfilling with approved material as drawings and technical specifications.@ Depth Up to 3m (mechanical means)	Cum	1680.77	
9	9.80	909 /91 0	Providing, laying, spreading, watering and compacting embankment with borrow material in layers not exceeding 150mm including haulage as per drawing and Technical Specifications. (Mechanical Means)	Cum	503.40	
10	9.9 B	909 /91 0	Providing, laying, spreading, watering and compacting embankment with Roadway Cutting material in layers not exceeding 150mm including haulage as per drawing and Technical	Cum	347.64	

Summary of Rates For Contractor

SN	Acti vity No.	SS Cla use	Description	Unit	Contractor Rate	Remarks
			Specifications. (Mechanical Means)			
11	9.9 B	909 /91 0	Providing suitable material and Back filling behind abutment, wing wall and return wall complete as per drawing and Technical Specifications. (Mechanical Means)	Cum	182.25	
12	9.11	908	Providing suitable material and Back filling behind abutment, wing wall and return wall complete as per drawing and Technical Specifications. (Manual means)	Cum	659.30	

4. Concrete Works

1	20.0 1	200 0	Providing and laying of PCC (Grade M 10) in foundation complete as per Drawing and Technical Specifications (1:3:6)	Cum	8723.31	
2	20.0 2.A	200 0	Providing and laying of PCC (Grade M 15) in foundation complete as per Drawing and Technical Specifications(1:2:4)	Cum	10089.59	

खण्ड ०८, संख्या ०४, मकवानपुर, श्रावण ३० गते, २०८१ साल

Summary of Rates For Contractor

SN	Acti vity No.	SS Cla use	Description	Unit	Contractor Rate	Remarks
3	20.0 2.B	200 0	Providing and laying of PCC (Grade M 20) in foundation complete as per Drawing and Technical Specifications(1:1.5:3)	Cum	11158.06	
4	20.0 2.C	200 0	Providing and laying of RCC (Grade M 20) in foundation complete as per Drawing and Technical Specifications (1:1.5:3)	Cum	11265.85	
5	20.0 2.D	200 0	Providing and laying of PCC (Grade M 25) in foundation complete as per Drawing and Technical Specifications (1:1:2)	Cum	12641.14	
6	20.0 2.E	200 0	Providing and laying of RCC (Grade M 25) in foundation complete as per Drawing and Technical Specifications(1:1:2)	Cum	12765.34	
7	20.3	200 0	Providing and laying, fitting and placing HYSD bar reinforcement in foundation complete as per Drawing and Technical Specifications (SS Clause 2014)	Ton	139725	
8	20.5	200 0	Providing and laying, fitting and placing HYSD bar reinforcement in sub-structure complete	Ton	139725	

Summary of Rates For Contractor

SN	Acti vity No.	SS Cla use	Description	Unit	Contractor Rate	Remarks
			as per Drawing and Technical Specifications (SS Clause 2014)			
9	20.0 4.A	200 0	Providing and laying of PCC (Grade M 15) in Sub Structure complete as per Drawing and Technical Specifications. (Height upto 5 m)(1:2:4)	Cum	10089.59	
10	20.0 4.B	200 0	Providing and laying of PCC (Grade M 20) in Sub Structure complete as per Drawing and Technical Specifications. (Height upto 5 m) (1:1.5:3)	Cum	11158.06	
11	20.0 4. C.p	200 0	Providing and laying of PCC (Grade M 25) in Sub Structure complete as per Drawing and Technical Specifications. (Height upto 5 m) (1:1:2)	Cum	12641.14	
12	20.0 4.E. p	200 0	Providing and laying of RCC (Grade M 20) in Sub Structure complete as per Drawing and Technical Specifications. (Height upto 5 m)(1:1.5:3)	Cum	11265.85	

Summary of Rates For Contractor

SN	Acti vity No.	SS Cla use	Description	Unit	Contractor Rate	Remarks
13	20.0 4. F.(p)	200 0	Providing and laying of RCC (Grade M 25) in sub-structure complete as per Drawing and Technical Specifications(1:1:2)	Cum	12765.34	
14	20.0 4. G.(p)	200 0	Providing and laying of RCC (Grade M 30) in sub-structure complete as per Drawing and Technical Specifications. (Height upto 5 m) (1:1.75:1.5)	Cum	12820.54	
15	20.0 4. H.p	200 0	Providing and laying of RCC (Grade M 35) in sub-structure complete as per Drawing and Technical Specifications. (Height upto 5 m)(1:1.5:1)	Cum	13074.46	

5. Brick Works

1	25.0 1 B	250 0	Providing and laying Brick Masonry Work in Cement mortar (cement:sand 1:3) in Foundation/Structure complete excluding pointing, plastering etc all complete as per Drawing and Technical Specifications	Cum	16284.27	
---	-------------	----------	---	-----	----------	--

Summary of Rates For Contractor

SN	Activity No.	SS Clause	Description	Unit	Contractor Rate	Remarks
2	25.0 1 C	250 0	Providing and laying Brick Masonry Work in Cement mortar (cement:sand 1:4) in Foundation/Structure complete excluding pointing, plastering etc all complete as per Drawing and Technical Specifications	Cum	15929.21	
3	25.0 1 D	250 0	Providing and laying Brick Masonry Work in Cement mortar (cement:sand 1:6) in Foundation/Structure complete excluding pointing, plastering etc all complete as per Drawing and Technical Specifications	Cum	15577.89	
4	25.0 3	250 0	Providing and applying pointing in Cement mortar (cement:sand 1:3) on brickwork in structure as per Drawing and Technical Specifications	Cum	289.99	
5	25.0 3	250 0	Providing and applying 12.5 mm thick Plaster with Cement mortar (cement:sand 1:3) on brickwork in structure	Cum	394.16	

Summary of Rates For Contractor

SN	Acti vity No.	SS Cla use	Description	Unit	Contractor Rate	Remarks
			as per Drawing and Technical Specifications			
6	25.0 3	250 0	Providing and applying 12.5 mm thick Plaster with Cement mortar (cement:sand 1:4) on brickwork in structure as per Drawing and Technical Specifications	Cum	374.98	

6. Masonry Works

1	26.1 0	260 2, 260 3, 260 8	Providing and laying dry Stone Masonry work as per Drawing and Technical Specifications	Cum	4164.15	
2	26.5 .A	260 0/2 607	Providing and laying Random Rubble Stone Masonry work in cement mortar 1:4 in structure including pointing works and providing necessary 100 mm dia HDPE pipes for weep holes etc all complete as per Drawing and Technical Specifications	Cum	9654.88	

Summary of Rates For Contractor

SN	Acti vity No.	SS Cla use	Description	Unit	Contractor Rate	Remarks
3	26.6 .A	260 0/2 607	Providing and laying Random Rubble Stone Masonry work in cement mortar 1:6 in structure including pointing works and providing necessary 100 mm dia HDPE pipes for weep holes etc all complete as per Drawing and Technical Specifications	Cum	9140.79	
4	26.7 0	260 0	Providing and Pointing with cement mortar 1:3 on masonry work in structure as per Technical Specifications	Cum	272.03	

7. Rver Training Works

1	24.1 A.i	240 1	Providing and Laying Gabion Structures for retaining earth with diapharagms including rolling, cutting, weaving, placing, laying sides and diaphragms with binding wire and filling stone / boulders including dressing, beding, bonding and all transportation all complete as per Drawing and Technical Specification.Hexagonal mesh type	Cum	5201.17	
---	-------------	----------	---	-----	---------	--

Summary of Rates For Contractor

SN	Acti vity No.	SS Cla use	Description	Unit	Contractor Rate	Remarks
			100mmx120mm using hexagonal Mesh wire - 10 SWG(0.0615 kg/m) & selvedge wire -8 SWG(0.1057kg/m) and Binding wire 12 SWG(0.0409kg/m) Box of different sizes as per requirements. (Size 3x1x1)			
2	24.1 A.ii	240 1	Providing and Laying Gabion Structures for retaining earth with diapharagms including rolling, cutting, weaving, placing, laying sides and diaphragms with binding wire and filling stone / boulders including dressing, beding, bonding and all transportation all complete as per Drawing and Technical Specification.Hexagonal mesh type 100mmx120mm using hexagonal Mesh wire - 10 SWG(0.0615 kg/m) & selvedge wire -8 SWG(0.1057kg/m) and Binding wire 12 SWG(0.0409kg/m) Box of different sizes as per	Cum	5286.54	

Summary of Rates For Contractor

SN	Activity No.	SS Clause	Description	Unit	Contractor Rate	Remarks
			requirements. (Size 2x1x1)			
3	24.1 A.iii	240 1	Providing and Laying Gabion Structures for retaining earth with diaphragms including rolling, cutting, weaving, placing, laying sides and diaphragms with binding wire and filling stone / boulders including dressing, beding, bonding and all transportation all complete as per Drawing and Technical Specification.Hexagonal mesh type 100mmx120mm using hexagonal Mesh wire - 10 SWG(0.0615 kg/m) & selvedge wire -8 SWG(0.1057kg/m) and Binding wire 12 SWG(0.0409kg/m) Box of different sizes as per requirements. (Size 1.5x1x1)	Cum	5681.96	

Summary of Rates For Contractor

SN	Activity No.	SS Clause	Description	Unit	Contractor Rate	Remarks
4	24.1 A.iii	240 1	Providing and Laying Gabion Structures for retaining earth with diaphragms including rolling, cutting, weaving, placing, laying sides and diaphragms with binding wire and filling stone / boulders including dressing, beding, bonding and all transportation all complete as per Drawing and Technical Specification.Hexagonal mesh type 100mmx120mm using hexagonal Mesh wire - 10 SWG(0.0615 kg/m) & selvedge wire -8 SWG(0.1057kg/m) and Binding wire 12 SWG(0.0409kg/m) Box of different sizes as per requirements. (Size 1x1x1)	Cum	5701.66	
5	24.1 A.vi ii	240 1	Providing and Laying Gabion Structures for retaining earth with diaphragms including rolling, cutting, weaving, placing, laying sides and diaphragms with binding wire and filling stone / boulders	Cum	6154.01	

Summary of Rates For Contractor

SN	Acti vity No.	SS Cla use	Description	Unit	Contractor Rate	Remarks
			including dressing, beding, bonding and all transportation all complete as per Drawing and Technical Specification.Hexagonal mesh type 100mmx120mm using hexagonal Mesh wire - 10 SWG(0.0615 kg/m) & selvedge wire -8 SWG(0.1057kg/m) and Binding wire 12 SWG(0.0409kg/m) Box of different sizes as per requirements. (Size 3x1x0.5)			
6	24.1 A.ix	240 1	Providing and Laying Gabion Structures for retaining earth with diapharagms including rolling, cutting, weaving, placing, laying sides and diaphragms with binding wire and filling stone / boulders including dressing, beding, bonding and all transportation all complete as per Drawing and Technical Specification.Hexagonal mesh type 100mmx120mm using hexagonal Mesh wire -	Cum	6415.09	

Summary of Rates For Contractor

SN	Acti vity No.	SS Cla use	Description	Unit	Contractor Rate	Remarks
			10 SWG(0.0615 kg/m) & selvedge wire -8 SWG(0.1057kg/m) and Binding wire 12 SWG(0.0409kg/m) Box of different sizes as per requirements. (Size 2x1x0.5)			
7	24.1 A.x	240 1	Providing and Laying Gabion Structures for retaining earth with diaphragms including rolling, cutting, weaving, placing, laying sides and diaphragms with binding wire and filling stone / boulders including dressing, beding, bonding and all transportation all complete as per Drawing and Technical Specification.Hexagonal mesh type 100mmx120mm using hexagonal Mesh wire - 10 SWG(0.0615 kg/m) & selvedge wire -8 SWG(0.1057kg/m) and Binding wire 12 SWG(0.0409kg/m) Box of different sizes as per requirements. (Size 1x1x0.5)	Cum	6934.52	

Summary of Rates For Contractor

SN	Activity No.	SS Clause	Description	Unit	Contractor Rate	Remarks
8	24.1 A.xi	240 1	Providing and Laying Gabion Structures for retaining earth with diaphragms including rolling, cutting, weaving, placing, laying sides and diaphragms with binding wire and filling stone / boulders including dressing, beding, bonding and all transportation all complete as per Drawing and Technical Specification.Hexagonal mesh type 100mmx120mm using hexagonal Mesh wire - 10 SWG(0.0615 kg/m) & selvedge wire -8 SWG(0.1057kg/m) and Binding wire 12 SWG(0.0409kg/m) Box of different sizes as per requirements. (Size 3x1x0.3)	Cum	7614.94	
9	24.1 A.xii	240 1	Providing and Laying Gabion Structures for retaining earth with diaphragms including rolling, cutting, weaving, placing, laying sides and diaphragms with binding wire and filling stone / boulders	Cum	7458.79	

Summary of Rates For Contractor

SN	Acti vity No.	SS Cla use	Description	Unit	Contractor Rate	Remarks
			including dressing, beding, bonding and all transportation all complete as per Drawing and Technical Specification.Hexagonal mesh type 100mmx120mm using hexagonal Mesh wire - 10 SWG(0.0615 kg/m) & selvedge wire -8 SWG(0.1057kg/m) and Binding wire 12 SWG(0.0409kg/m) Box of different sizes as per requirements. (Size 2x1x0.3)			
10	24.1 A.xii i	240 1	Providing and Laying Gabion Structures for retaining earth with diapharagms including rolling, cutting, weaving, placing, laying sides and diaphragms with binding wire and filling stone / boulders including dressing, beding, bonding and all transportation all complete as per Drawing and Technical Specification.Hexagonal mesh type 100mmx120mm using hexagonal Mesh wire -	Cum	6738.49	

Summary of Rates For Contractor

SN	Acti vity No.	SS Cla use	Description	Unit	Contractor Rate	Remarks
			10 SWG(0.0615 kg/m) & selvedge wire -8 SWG(0.1057kg/m) and Binding wire 12 SWG(0.0409kg/m) Box of different sizes as per requirements. (Size 1x1x0.3)			
Machine Made gabion Box						
11	24.1 A.xii i	240 2	Supply of Machine Made Gabion boxes / mattresses with diapharagms including rolling, cutting and weaving as per specification. Including Providing and filling stone / boulder in gabion boxes / mattress etc. including dressing, beding, bonding and all transportation as per Specification.Hexagonal mesh type 100mmx120mm using hexagonal Mesh wire - 3mm , selvedge wire - 3.9mm and Lacing wire 2.4mm Heavy Zinc Coating Box of different sizes as per requirements. (Size 1x1x1)	Cum	4371.15	

Summary of Rates For Contractor

SN	Acti vity No.	SS Cla use	Description	Unit	Contractor Rate	Remarks
12	24.2 A & 24.4	240 2	Supply of Machine Made Gabion boxes / mattresses with diapharagms including rolling, cutting and weaving as per specification. Including Providing and filling stone / boulder in gabion boxes / mattress etc. including dressing, beding, bonding and all transportation as per Specification.Hexagonal mesh type 100mmx120mm using hexagonal Mesh wire - 3mm , selvedge wire - 3.9mm and Lacing wire 2.4mm Heavy Zinc Coating Box of different sizes as per requirements. (Size 2x1x1)	Cum	4213.03	
13	24.2 A & 24.4	240 2	Supply of Machine Made Gabion boxes / mattresses with diapharagms including rolling, cutting and weaving as per specification. Including Providing and filling stone / boulder in gabion boxes / mattress etc. including dressing,	Cum	4160.32	

Summary of Rates For Contractor

SN	Acti vity No.	SS Cla use	Description	Unit	Contractor Rate	Remarks
			beding, bonding and all transportation as per Specification.Hexagonal mesh type 100mmx120mm using hexagonal Mesh wire - 3mm , selvedge wire - 3.9mm and Lacing wire 2.4mm Heavy Zinc Coating Box of different sizes as per requirements. (Size 1.5x1x1)			
14	24.2 A & 24.4	240 2	Supply of Machine Made Gabion boxes / mattresses with diapharagms including rolling, cutting and weaving as per specification. Including Providing and filling stone / boulder in gabion boxes / mattress etc. including dressing, beding, bonding and all transportation as per Specification.Hexagonal mesh type 100mmx120mm using hexagonal Mesh wire - 3mm , selvedge wire - 3.9mm and Lacing wire 2.4mm Heavy Zinc Coating Box of different sizes as per	Cum	4160.32	

खण्ड ०८, संख्या ०४, मकवानपुर, श्रावण ३० गते, २०८१ साल

Summary of Rates For Contractor

SN	Acti vity No.	SS Cla use	Description	Unit	Contractor Rate	Remarks
			requirements. (Size 3x1x1)			
15	24.5 0	240 4	Providing and laying of a geotextile filter between pitching and embankment slopes as per Drawing and Technical Specifications.	Sqm	156.19	
16	24.2 1.A. I	242 1	Providing and laying Plum Concrete mixing of 60% M15 concrete and 40% boulder/stones (Boulder mixed concrete) including pipes for weep holes etc all complete as per Drawing and Technical Specifications. (Mechanical Means)	Cum	8876.29	
17	24.2 1.B. I	242 1	Providing and laying Plum Concrete mixing of 70% M15 concrete and 30% boulder/stones (Boulder mixed concrete) including pipes for weep holes etc all complete as per Drawing and Technical	Cum	9544.52	

Summary of Rates For Contractor

SN	Acti vity No.	SS Cla use	Description	Unit	Contractor Rate	Remarks
			Specifications. (Mechanical Means)			
18	24.2 1.B. I	242 1	Providing and laying HDPE pipes with perforations including joining series II, HDPE pipe 250 mm dia. Unit = meter (For 100 m.)	Rm	911.77	

8. Miscellaneous Works

1	9.80	909 /91 0	Providing suitable material and Back filling behind abutment, wing wall and return wall complete as per drawing and Technical Specifications. (Mechanical Means)	Cum	163.56	
2	9.11	908	Providing suitable material and Back filling behind abutment, wing wall and return wall complete as per drawing and Technical Specifications. (Manual means)	Cum	690.28	

Summary of Rates For Contractor

SN	Acti vity No.	SS Cla use	Description	Unit	Contractor Rate	Remarks
3	10.4 case I	100 3/1 005	Loosening of the ground upto a level of 500mm below the sub-grade level , watering, graded and compacted in layers as per Drawing and Technical Specification (compacting orginal ground supporting sub-grade)	Cum	126.24	
4	12.1 A	120 1	Providing and laying granular sub-base on prepared surface, mixing at OMC, and compacting to achieve the desired density by mechanical means, complete as per Drawing and Technical Specifications.	Cum	2108.53	
5	10.8	100 0	Providing and laying of hand pack Stone soling with 150 to 200 mm thick stones and packing with smaller stone on prepared surface as per Drawing and	Cum	3550.05	

Summary of Rates For Contractor

SN	Acti vity No.	SS Cla use	Description	Unit	Contractor Rate	Remarks
			Technical Specifications.			
6	18.2 .a.i	180 4, 180 5	Providing, Preparing and Installing form work including necessary supports and removing after completion for Foundation and footings. (Class F1 Finish).	Sqm	810.20	
7	18.2 .a.i	180 4, 180 5	Providing, Preparing and Installing form work including necessary supports and removing after completion for walls. (Class F2 Finish), vertical plain surface.	Sqm	822.78	

9. Rate Analysis for Loading and Unloading of Materials (excluding Transportation)

1	8.9 A	800	Loading and Unloading of Stone Boulder/ aggregates/ Sand/ excavated earth etc. by Mechanical means. Placing tipper at loading point, loading with front end loader, dumping, turning for return trip,	Cum	275.06	
---	----------	-----	---	-----	--------	--

खण्ड ०८, संख्या ०४, मकवानपुर, श्रावण ३० गते, २०८१ साल

Summary of Rates For Contractor

SN	Acti vity No.	SS Cla use	Description	Unit	Contractor Rate	Remarks
			excluding time for haulage and return trip.			
2	8.9 B	800	Loading and Unloading of Stone Boulder/ aggregates/ Sand/ excavated earth etc. by Manual means.	Cum	369.68	
3	8.10	800	Loading and Unloading of Cement or Steel by Manual means and Stacking.	Tonn	794.02	
4	8.11	800	Loading and Unloading of Bricks by Manual means and Stacking.	no.	1.29	
5	8.12	800	Loading and Unloading of Bitumen drums by Manual means.	Tonn	595.51	
6	8.13	800	Loading and Unloading of Timber by Manual means.	Tonn	906.91	
7	8.14	800	Loading and Unloading of Cement Concrete Blocks, Kerbs etc.	Cum	1360.36	
8	8.15 .i.A & 8.15 .ii.A	800	Loading and Unloading of RCC Hume Pipes by Mechanical means including a lead upto 30m. A) 900/1000/1200 mm dia RCC Hume Pipe	Rm	904.85	

Summary of Rates For Contractor

SN	Acti vity No.	SS Cla use	Description	Unit	Contractor Rate	Remarks
9	8.15 .i.B & 8.15 .ii.B	800	Loading and Unloading of RCC Hume Pipes by Mechanical means including a lead upto 30m. B) 750/600 mm dia RCC Hume Pipe	Rm	564.71	
10	8.15 .i.C & 8.15 .ii.C	800	Loading and Unloading of RCC Hume Pipes by Mechanical means including a lead upto 30m. C) 450/300 mm dia RCC Hume Pipe	Rm	361.94	
11	8.15 .iii.A & 8.15 .iv.A	800	Loading and Unloading of RCC Hume Pipes by manual means including a lead upto 30m. A) 900/1000/1200 mm dia RCC Hume Pipe	Rm	1776.13	
12	8.15 .iii.B & 8.15 .iv.B	800	Loading and Unloading of RCC Hume Pipes by manual means including a lead upto 30m. B) 750/600 mm dia RCC Hume Pipe	Rm	1115.42	
13	8.15 .iii.C & 8.15 .iv.C	800	Loading and Unloading of RCC Hume Pipes by manual means including a lead upto 30m. C) 450/300 mm dia RCC Hume Pipe	Rm	771.41	

Summary of Rates For Users Community

SN	Activit y No.	SS Clau se	Description	Unit	Users com mitte e Rate	Re ma rk s
<u>1. Site Clearance</u>						
1	7.1 A	201	Clearing and grubbing road land including uprooting rank vegetation, grass, bushes, shrubs, saplings and trees girth up to 300 mm, removal of stumps of trees cut earlier and disposal of unserviceable materials and stacking of serviceable Material to be used or auctioned, up to a lead of 30 meters including removal and disposal of top organic soil not exceeding 150 mm in thickness. By Mechanical Means In area of light jungle (less than 15 number per 100 sqm, Unit = sqm, (for 10,000 sqm))	Sqm	4.87	
2	2.2	201	Cutting of Trees, including cutting of Trunks, Branches and Removal Cutting of trees, including cutting of trunks, branches and removal of stumps, roots, stacking of serviceable Material with all lifts and up to a lead of 1000 meters and earth filling in the depression/pit. Unit = Number (for 30 number) (i) Girth from 300 mm to 900 mm	no.	958.1 3	
<u>2. Pipe Drains</u>						

Summary of Rates For Users Community

SN	Activity No.	SS Clause	Description	Unit	Users committee Rate	Remarks
1	7.1 A	701	Providing, Jointing and Laying HDPE Pipes with or without collar etc. complete in place as per Drawing and Technical Specifications (Size 110mm/125 mm outer dia.)	Rm	671.36	
2	7.2 A	701	Providing and Laying RCC 300mm dia NP3 Flush jointed pipe for culvert including fixing with cement mortar 1:2 as per drawing and technical specifications	Rm	4238.47	
3	7.2 B	701	Providing and Laying RCC 450mm dia NP3 Flush jointed pipe for culvert including fixing with cement mortar 1:2 as per drawing and technical specifications	Rm	6049.54	
4	7.2.C	701	Providing and Laying RCC 600mm dia NP3 Flush jointed pipe for culvert including fixing with cement mortar 1:2 as per drawing and technical specifications	Rm	8231.26	
5	7.2 D	701	Providing and Laying RCC 900mm dia NP3 Flush jointed pipe for culvert including fixing with cement mortar 1:2 as per drawing and technical specifications	Rm	14973.82	
<u>3. Earth Works In Excavation</u>						

खण्ड ०८, संख्या ०४, मकवानपुर, श्रावण ३० गते, २०८१ साल

Summary of Rates For Users Community

SN	Activity No.	SS Clause	Description	Unit	Users committee Rate	Remarks
1	9.1.I.B	905	Roadway excavation in all types of soil as per Drawing and Technical Specification including removal of stumps and other deleterious matter, all lift and leads as per Drawing and Instruction of the Engineer.	Cum	71.02	
2	9.1.I.B	905	Roadway excavation in ordinary rock as per Drawing and Technical Specification including all lift and leads as per Drawing and Instruction of the Engineer. (Mechanical Means)	Cum	213.06	
3	9.1.IV. A	905	Roadway excavation in hard rock with rock breakers including breaking rock lift and lead for disposal as per Drawing and Technical Specification. (Mechanical Means)	Cum	1400.52	
4	9.4.I.B. i	907	Earthwork in excavation of foundation of structure in ordinary soil including construction of shoring and bracing, removal of stumps and other deleterious matter and backfilling with approved material as drawings and technical specifications.@ Depth upto 3m (mechanical means)	Cum	106.53	

Summary of Rates For Users Community

SN	Activity No.	SS Clause	Description	Unit	Users committee Rate	Remarks
5	9.4.I.B. ii	907	Earthwork in excavation of foundation of structure in ordinary soil including construction of shoring and bracing, removal of stumps and other deleterius matter and backfilling with approved material as drawings and technical specifications.@ Depth 3 to 6m (mechanical means)	Cum	121.7 5	
6	9.4.I.B. iii	907	Earthwork in excavation of foundation of structure in ordinary soil including construction of shoring and bracing, removal of stumps and other deleterius matter and backfilling with approved material as drawings and technical specifications.@ Depth above 6m (mechanical means)	Cum	153.5 1	
7	9.4.II.B .	907	Earthwork in excavation of foundation of structure in ordinary Rock including construction of shoring and bracing, removal of stumps and other deleterius matter and backfilling with approved material as drawings and technical specifications.@ Depth Up to 3m (mechanical means)	Cum	284.0 9	

Summary of Rates For Users Community

SN	Activit y No.	SS Clau se	Description	Unit	Users com mitte e Rate	Re ma rk s
8	9.4.IV. A.	907	Earthwork in excavation of foundation of structure in Hard Rock including construction of shoring and bracing, removal of stumps and other deleterious matter and backfilling with approved material as drawings and technical specifications.@ Depth Up to 3m (mechanical means)	Cum	1504. 03	
9	9.80	909/ 910	Providing, laying, spreading, watering and compacting embankment with borrow material in layers not exceeding 150mm including haulage as per drawing and Technical Specifications. (Mechanical Means)	Cum	445.6 1	
10	9.9 B	909/ 910	Providing, laying, spreading, watering and compacting embankment with Roadway Cutting material in layers not exceeding 150mm including haulage as per drawing and Technical Specifications. (Mechanical Means)	Cum	313.8 9	
11	9.9 B	909/ 910	Providing suitable material and Back filling behind abutment, wing wall and return wall complete as per drawing and Technical Specifications. (Mechanical Means)	Cum	161.2 0	

Summary of Rates For Users Community

SN	Activity No.	SS Clause	Description	Unit	Users committee Rate	Remarks
12	9.11	908	Providing suitable material and Back filling behind abutment, wing wall and return wall complete as per drawing and Technical Specifications. (Manual means)	Cum	580.34	
<u>4. Concrete Works</u>						
1	20.01	2000	Providing and laying of PCC (Grade M 10) in foundation complete as per Drawing and Technical Specifications (1:3:6)	Cum	7254.48	
2	20.02. A	2000	Providing and laying of PCC (Grade M 15) in foundation complete as per Drawing and Technical Specifications(1:2:4)	Cum	8643.36	
3	20.02. B	2000	Providing and laying of PCC (Grade M 20) in foundation complete as per Drawing and Technical Specifications(1:1.5:3)	Cum	9750.62	
4	20.02. C	2000	Providing and laying of RCC (Grade M 20) in foundation complete as per Drawing and Technical Specifications (1:1.5:3)	Cum	9974.18	
5	20.02. D	2000	Providing and laying of PCC (Grade M 25) in foundation complete as per Drawing and Technical Specifications (1:1:2)	Cum	11206.45	
6	20.02. E	2000	Providing and laying of RCC (Grade M 25) in foundation complete as per Drawing and Technical Specifications(1:1:2)	Cum	11446.13	

खण्ड ०८, संख्या ०४, मकवानपुर, श्रावण ३० गते, २०८१ साल

Summary of Rates For Users Community

SN	Activit y No.	SS Clau se	Description	Unit	Users com mitte e Rate	Re ma rk s
7	20.3	2000	Providing and laying, fitting and placing HYSD bar reinforcement in foundation complete as per Drawing and Technical Specifications (SS Clause 2014)	Ton	1356 49.2	
8	20.5	2000	Providing and laying, fitting and placing HYSD bar reinforcement in sub-structure complete as per Drawing and Technical Specifications (SS Clause 2014)	Ton	1356 49.2	
9	20.04. A	2000	Providing and laying of PCC (Grade M 15) in Sub Structure complete as per Drawing and Technical Specifications. (Height upto 5 m)(1:2:4)	Cum	8643. 36	
10	20.04. B	2000	Providing and laying of PCC (Grade M 20) in Sub Structure complete as per Drawing and Technical Specifications. (Height upto 5 m) (1:1.5:3)	Cum	9750. 62	
11	20.04. C.p	2000	Providing and laying of PCC (Grade M 25) in Sub Structure complete as per Drawing and Technical Specifications. (Height upto 5 m) (1:1:2)	Cum	1120 6.45	
12	20.04. E.p	2000	Providing and laying of RCC (Grade M 20) in Sub Structure complete as per Drawing and Technical Specifications. (Height upto 5 m)(1:1.5:3)	Cum	9974. 18	

Summary of Rates For Users Community

SN	Activit y No.	SS Clau se	Description	Unit	Users com mitte e Rate	Re ma rk s
13	20.04. F.(p)	2000	Providing and laying of RCC (Grade M 25) in sub-structure complete as per Drawing and Technical Specifications(1:1:2)	Cum	1144 6.13	
14	20.04. G.(p)	2000	Providing and laying of RCC (Grade M 30) in sub-structure complete as per Drawing and Technical Specifications. (Height upto 5 m) (1:1.75:1.5)	Cum	1150 0.37	
15	20.04. H.p	2000	Providing and laying of RCC (Grade M 35) in sub-structure complete as per Drawing and Technical Specifications. (Height upto 5 m)(1:1.5:1)	Cum	1174 9.88	

5. Brick Works

1	25.01 B	2500	Providing and laying Brick Masonry Work in Cement mortar (cement:sand 1:3) in Foundation/Structure complete excluding pointing, plastering etc all complete as per Drawing and Technical Specifications	Cum	1548 6.42	
2	25.01 C	2500	Providing and laying Brick Masonry Work in Cement mortar (cement:sand 1:4) in Foundation/Structure complete excluding pointing,	Cum	1513 3.73	

Summary of Rates For Users Community

SN	Activity No.	SS Clause	Description	Unit	Users committee Rate	Remarks
			plastering etc all complete as per Drawing and Technical Specifications			
3	25.01 D	2500	Providing and laying Brick Masonry Work in Cement mortar (cement:sand 1:6) in Foundation/Structure complete excluding pointing, plastering etc all complete as per Drawing and Technical Specifications	Cum	1478 4.29	
4	25.03	2500	Providing and applying pointing in Cement mortar (cement:sand 1:3) on brickwork in structure as per Drawing and Technical Specifications	Cum	254.7 0	
5	25.03	2500	Providing and applying 12.5 mm thick Plaster with Cement mortar (cement:sand 1:3) on brickwork in structure as per Drawing and Technical Specifications	Cum	354.9 1	
6	25.03	2500	Providing and applying 12.5 mm thick Plaster with Cement mortar (cement:sand 1:4) on brickwork in structure as per Drawing and Technical Specifications	Cum	335.8 7	
<u>6. Masonary Works</u>						

Summary of Rates For Users Community

SN	Activity No.	SS Clause	Description	Unit	Users committee Rate	Remarks
1	26.10	2602 , 2603 , 2608	Providing and laying dry Stone Masonry work as per Drawing and Technical Specifications	Cum	3621.00	
2	26.5.A	2600 /2607	Providing and laying Random Rubble Stone Masonry work in cement mortar 1:4 in structure including pointing works and providing necessary 100 mm dia HDPE pipes for weep holes etc all complete as per Drawing and Technical Specifications	Cum	8635.33	
3	26.6.A	2600 /2607	Providing and laying Random Rubble Stone Masonry work in cement mortar 1:6 in structure including pointing works and providing necessary 100 mm dia HDPE pipes for weep holes etc all complete as per Drawing and Technical Specifications	Cum	8124.41	
4	26.70	2600	Providing and Pointing with cement mortar 1:3 on masonry work in structure as per Technical Specifications	Cum	241.79	

7. Rver Training Works

Summary of Rates For Users Community

SN	Activity No.	SS Clause	Description	Unit	Users committee Rate	Remarks
1	24.1 A.i	2401	Providing and Laying Gabion Structures for retaining earth with diaphragms including rolling, cutting, weaving, placing, laying sides and diaphragms with binding wire and filling stone / boulders including dressing, beding, bonding and all transportation all complete as per Drawing and Technical Specification.Hexagonal mesh type 100mmx120mm using hexagonal Mesh wire -10 SWG(0.0615 kg/m) & selvedge wire -8 SWG(0.1057kg/m) and Binding wire 12 SWG(0.0409kg/m) Box of different sizes as per requirements. (Size 3x1x1)	Cum	4742.93	
2	24.1 A.ii	2401	Providing and Laying Gabion Structures for retaining earth with diaphragms including rolling, cutting, weaving, placing, laying sides and diaphragms with binding wire and filling stone / boulders including dressing, beding, bonding and all transportation all complete as per Drawing and Technical Specification.Hexagonal mesh type 100mmx120mm using hexagonal Mesh wire -10 SWG(0.0615 kg/m) & selvedge	Cum	4826.81	

Summary of Rates For Users Community

SN	Activity No.	SS Clause	Description	Unit	Users committee Rate	Remarks
			wire -8 SWG(0.1057kg/m) and Binding wire 12 SWG(0.0409kg/m) Box of different sizes as per requirements. (Size 2x1x1)			
3	24.1 A.iii	2401	Providing and Laying Gabion Structures for retaining earth with diaphragms including rolling, cutting, weaving, placing, laying sides and diaphragms with binding wire and filling stone / boulders including dressing, beding, bonding and all transportation all complete as per Drawing and Technical Specification.Hexagonal mesh type 100mmx120mm using hexagonal Mesh wire -10 SWG(0.0615 kg/m) & selvedge wire -8 SWG(0.1057kg/m) and Binding wire 12 SWG(0.0409kg/m) Box of different sizes as per requirements. (Size 1.5x1x1)	Cum	5196.28	

Summary of Rates For Users Community

SN	Activity No.	SS Clause	Description	Unit	Users committee Rate	Remarks
4	24.1 A.iii	2401	Providing and Laying Gabion Structures for retaining earth with diaphragms including rolling, cutting, weaving, placing, laying sides and diaphragms with binding wire and filling stone / boulders including dressing, beding, bonding and all transportation all complete as per Drawing and Technical Specification.Hexagonal mesh type 100mmx120mm using hexagonal Mesh wire -10 SWG(0.0615 kg/m) & selvedge wire -8 SWG(0.1057kg/m) and Binding wire 12 SWG(0.0409kg/m) Box of different sizes as per requirements. (Size 1x1x1)	Cum	5215.64	
5	24.1 A.viii	2401	Providing and Laying Gabion Structures for retaining earth with diaphragms including rolling, cutting, weaving, placing, laying sides and diaphragms with binding wire and filling stone / boulders including dressing, beding, bonding and all transportation all complete as per Drawing and Technical Specification.Hexagonal mesh type 100mmx120mm using hexagonal Mesh wire -10 SWG(0.0615 kg/m) & selvedge	Cum	5660.13	

Summary of Rates For Users Community

SN	Activity No.	SS Clause	Description	Unit	Users committee Rate	Remarks
			wire -8 SWG(0.1057kg/m) and Binding wire 12 SWG(0.0409kg/m) Box of different sizes as per requirements. (Size 3x1x0.5)			
6	24.1 A.ix	2401	Providing and Laying Gabion Structures for retaining earth with diaphragms including rolling, cutting, weaving, placing, laying sides and diaphragms with binding wire and filling stone / boulders including dressing, beding, bonding and all transportation all complete as per Drawing and Technical Specification.Hexagonal mesh type 100mmx120mm using hexagonal Mesh wire -10 SWG(0.0615 kg/m) & selvedge wire -8 SWG(0.1057kg/m) and Binding wire 12 SWG(0.0409kg/m) Box of different sizes as per requirements. (Size 2x1x0.5)	Cum	5897.6	

Summary of Rates For Users Community

SN	Activity No.	SS Clause	Description	Unit	Users committee Rate	Remarks
7	24.1 A.x	2401	Providing and Laying Gabion Structures for retaining earth with diaphragms including rolling, cutting, weaving, placing, laying sides and diaphragms with binding wire and filling stone / boulders including dressing, beding, bonding and all transportation all complete as per Drawing and Technical Specification.Hexagonal mesh type 100mmx120mm using hexagonal Mesh wire -10 SWG(0.0615 kg/m) & selvedge wire -8 SWG(0.1057kg/m) and Binding wire 12 SWG(0.0409kg/m) Box of different sizes as per requirements. (Size 1x1x0.5)	Cum	6382.32	
8	24.1 A.xi	2401	Providing and Laying Gabion Structures for retaining earth with diaphragms including rolling, cutting, weaving, placing, laying sides and diaphragms with binding wire and filling stone / boulders including dressing, beding, bonding and all transportation all complete as per Drawing and Technical Specification.Hexagonal mesh type 100mmx120mm using hexagonal Mesh wire -10 SWG(0.0615 kg/m) & selvedge	Cum	7045.81	

Summary of Rates For Users Community

SN	Activity No.	SS Clause	Description	Unit	Users committee Rate	Remarks
			wire -8 SWG(0.1057kg/m) and Binding wire 12 SWG(0.0409kg/m) Box of different sizes as per requirements. (Size 3x1x0.3)			
9	24.1 A.xii	2401	Providing and Laying Gabion Structures for retaining earth with diaphragms including rolling, cutting, weaving, placing, laying sides and diaphragms with binding wire and filling stone / boulders including dressing, beding, bonding and all transportation all complete as per Drawing and Technical Specification.Hexagonal mesh type 100mmx120mm using hexagonal Mesh wire -10 SWG(0.0615 kg/m) & selvedge wire -8 SWG(0.1057kg/m) and Binding wire 12 SWG(0.0409kg/m) Box of different sizes as per requirements. (Size 2x1x0.3)	Cum	6923.14	

Summary of Rates For Users Community

SN	Activity No.	SS Clause	Description	Unit	Users committee Rate	Remarks
10	24.1 A.xiii	2401	Providing and Laying Gabion Structures for retaining earth with diaphragms including rolling, cutting, weaving, placing, laying sides and diaphragms with binding wire and filling stone / boulders including dressing, beding, bonding and all transportation all complete as per Drawing and Technical Specification.Hexagonal mesh type 100mmx120mm using hexagonal Mesh wire -10 SWG(0.0615 kg/m) & selvedge wire -8 SWG(0.1057kg/m) and Binding wire 12 SWG(0.0409kg/m) Box of different sizes as per requirements. (Size 1x1x0.3)	Cum	6215.37	
Machine Made gabion Box						
11	24.1 A.xiii	2402	Supply of Machine Made Gabion boxes / mattresses with diaphragms including rolling, cutting and weaving as per specification. Including Providing and filling stone / boulder in gabion boxes / mattress etc. including dressing, beding, bonding and all transportation as per Specification.Hexagonal mesh type 100mmx120mm using hexagonal Mesh wire -3mm ,	Cum	4015.5	

Summary of Rates For Users Community

SN	Activity No.	SS Clause	Description	Unit	Users committee Rate	Remarks
			selvedge wire -3.9mm and Lacing wire 2.4mm Heavy Zinc Coating Box of different sizes as per requirements. (Size 1x1x1)			
12	24.2 A & 24.4	2402	Supply of Machine Made Gabion boxes / mattresses with diaphragms including rolling, cutting and weaving as per specification. Including Providing and filling stone / boulder in gabion boxes / mattress etc. including dressing, beding, bonding and all transportation as per Specification.Hexagonal mesh type 100mmx120mm using hexagonal Mesh wire -3mm , selvedge wire -3.9mm and Lacing wire 2.4mm Heavy Zinc Coating Box of different sizes as per requirements. (Size 2x1x1)	Cum	3860.13	
13	24.2 A & 24.4	2402	Supply of Machine Made Gabion boxes / mattresses with diaphragms including rolling, cutting and weaving as per specification. Including Providing and filling stone / boulder in gabion boxes / mattress etc. including dressing, beding,	Cum	3808.33	

Summary of Rates For Users Community

SN	Activity No.	SS Clause	Description	Unit	Users committee Rate	Remarks
			bonding and all transportation as per Specification.Hexagonal mesh type 100mmx120mm using hexagonal Mesh wire -3mm , selvedge wire -3.9mm and Lacing wire 2.4mm Heavy Zinc Coating Box of different sizes as per requirements. (Size 1.5x1x1)			
14	24.2 A & 24.4	2402	Supply of Machine Made Gabion boxes / mattresses with diaphragms including rolling, cutting and weaving as per specification. Including Providing and filling stone / boulder in gabion boxes / mattress etc. including dressing, beding, bonding and all transportation as per Specification.Hexagonal mesh type 100mmx120mm using hexagonal Mesh wire -3mm , selvedge wire -3.9mm and Lacing wire 2.4mm Heavy Zinc Coating Box of different sizes as per requirements. (Size 3x1x1)	Cum	3808.33	
15	24.50	2404	Providing and laying of a geotextile filter between pitching and embankment slopes as per Drawing and Technical Specifications.	Sqm	152.2	

Summary of Rates For Users Community

SN	Activit y No.	SS Clau se	Description	Unit	Users com mitte e Rate	Re ma rk s
16	24.21. A.I	2421	Providing and laying Plum Concrete mixing of 60% M15 concrete and 40% boulder/stones (Boulder mixed concrete) including pipes for weep holes etc all complete as per Drawing and Technical Specifications. (Mechanical Means)	Cum	7616.7 6	
17	24.21. B.I	2421	Providing and laying Plum Concrete mixing of 70% M15 concrete and 30% boulder/stones (Boulder mixed concrete) including pipes for weep holes etc all complete as per Drawing and Technical Specifications. (Mechanical Means)	Cum	8176.7 3	
18	24.21. B.I	2421	Providing and laying HDPE pipes with perforations including joining series II, HDPE pipe 250 mm dia. Unit = meter (For 100 m.)	Rm	865.24	

8. Miscellaneous Works

1	9.80	909/ 910	Providing suitable material and Back filling behind abutment, wing wall and return wall complete as per drawing and Technical Specifications. (Mechanical Means)	Cum	148.8 0	
---	------	-------------	--	-----	------------	--

Summary of Rates For Users Community

SN	Activity No.	SS Clause	Description	Unit	Users committee Rate	Remarks
2	9.11	908	Providing suitable material and Back filling behind abutment, wing wall and return wall complete as per drawing and Technical Specifications. (Manual means)	Cum	608.88	
3	10.4 case I	1003 /1005	Loosening of the ground upto a level of 500mm below the sub-grade level , watering, graded and compacted in layers as per Drawing and Technical Specification (compacting original ground supporting sub-grade)	Cum	116.62	
4	12.1 A	1201	Providing and laying granular sub-base on prepared surface, mixing at OMC, and compacting to achieve the desired density by mechanical means, complete as per Drawing and Technical Specifications.	Cum	1850.96	
5	10.8	1000	Providing and laying of hand pack Stone soling with 150 to 200 mm thick stones and packing with smaller stone on prepared surface as per Drawing and Technical Specifications.	Cum	3087.00	

Summary of Rates For Users Community

SN	Activit y No.	SS Clau se	Description	Unit	Users com mitte e Rate	Re ma rk s
6	18.2.a.i	1804 , 1805	Providing, Preparing and Installing form work including necessary supports and removing after completion for Foundation and footings. (Class F1 Finish).	Sqm	750.1 2	
7	18.2.a.i	1804 , 1805	Providing, Preparing and Installing form work including necessary supports and removing after completion for walls. (Class F2 Finish), vertical plain surface.	Sqm	749.4 1	

9. Rate Analysis for Loading and Unloading of Materials (excluding Transportation)

1	8.9 A	800	Loading and Unloading of Stone Boulder/ aggregates/ Sand/ excavated earth etc. by Mechanical means. Placing tipper at loading point, loading with front end loader, dumping, turning for return trip, excluding time for haulage and return trip.	Cum	258.3 2	
2	8.9 B	800	Loading and Unloading of Stone Boulder/ aggregates/ Sand/ excavated earth etc. by Manual means.	Cum	339.2 2	

खण्ड ०८, संख्या ०४, मकवानपुर, श्रावण ३० गते, २०८१ साल

Summary of Rates For Users Community

SN	Activity No.	SS Clause	Description	Unit	Users committee Rate	Remarks
3	8.10	800	Loading and Unloading of Cement or Steel by Manual means and Stacking.	Tonn	732.07	
4	8.11	800	Loading and Unloading of Bricks by Manual means and Stacking.	no.	1.20	
5	8.12	800	Loading and Unloading of Bitumen drums by Manual means.	Tonn	549.05	
6	8.13	800	Loading and Unloading of Timber by Manual means.	Tonn	830.24	
7	8.14	800	Loading and Unloading of Cement Concrete Blocks, Kerbs etc.	Cum	1245.36	
8	8.15.i. A & 8.15.ii. A	800	Loading and Unloading of RCC Hume Pipes by Mechanical means including a lead upto 30m. A) 900/1000/1200 mm dia RCC Hume Pipe	Rm	827.16	
9	8.15.i. B & 8.15.ii. B	800	Loading and Unloading of RCC Hume Pipes by Mechanical means including a lead upto 30m. B) 750/600 mm dia RCC Hume Pipe	Rm	515.25	
10	8.15.i. C & 8.15.ii. C	800	Loading and Unloading of RCC Hume Pipes by Mechanical means including a lead upto 30m. C) 450/300 mm dia RCC Hume Pipe	Rm	330.86	

खण्ड ०८, संख्या ०४, मकवानपुर, श्रावण ३० गते, २०८१ साल

Summary of Rates For Users Community

SN	Activity No.	SS Clause	Description	Unit	Users committee Rate	Remarks
11	8.15.iii .A & 8.15.iv. A	800	Loading and Unloading of RCC Hume Pipes by manual means including a lead upto 30m. A) 900/1000/1200 mm dia RCC Hume Pipe	Rm	1641.58	
12	8.15.iii .B & 8.15.iv. B	800	Loading and Unloading of RCC Hume Pipes by manual means including a lead upto 30m. B) 750/600 mm dia RCC Hume Pipe	Rm	1021.20	
13	8.15.iii .C & 8.15.iv. C	800	Loading and Unloading of RCC Hume Pipes by manual means including a lead upto 30m. C) 450/300 mm dia RCC Hume Pipe	Rm	704.97	

सिभिल (जेनरल/भवन निर्माण सम्बन्धि) कार्यको आईटम दर रेट साराशं-२०८१/०८२

सि.नं.	आईटम नं.	कामको विवरण	इकाई		आईटम दर (ठेक्काबाट)	आईटम दर (उपभोक्त गबाट)	८१/८ २ (ठेक्काबाट)
कार्य समूह 'क' :- साईट सफा गर्ने काम							

खण्ड ०८, संख्या ०४, मकवानपुर, श्रावण ३० गते, २०८१ साल

सिभिल (जेनरल/भवन निर्माण सम्बन्धि) कार्यको आईटम दर रेट सारांश-२०८१/०८२

सि.नं.	आईटम नं.	कामको विवरण	इकाई		आईटम दर (ठेक्काबाट)	आईटम दर (उपभोक्त गबाट)	८१/८ २ (ठेक्काबा ट)
१	१-१ क	१२-३० से.मी. गोलाईको रुख ढाल्ने कार्य हाँगाहरु काटी रुखको टुक्रा पारी निर्माण स्थलबाट १५ मीटर दूरीसम्म बोकानी गर्ने कार्य समेत ।	Ps	रु.	131.56	114.40	
२	१-१ ख	१३७ से.मी.गोलाईको रुख ढाल्ने कार्य हाँगाहरु काटी रुखलाई टुक्रा पारी निर्माण स्थलबाट १५ मीटर दुरीसम्म बोकनी गर्ने आदी कार्य समेत	Ps	रु.	4048.00	3520.0 0	
३	१-२ क	१२-३० से.मी. गोलाईको रुख जरा भिक्ने कार्य जरा उठाउने र निर्माण स्थलबाट १५ मीटर दुरीसम्म बोकनी गर्ने आदी कार्य समेत	Ps	रु.	404.80	352.00	
४	१-३	बाक्लो भारपात काट्ने जरा भिक्ने र निर्माण स्थलबाट २५ मीटर दूरीसम्म बोकानी गर्ने आदि कार्य समेत	Ps	रु.	40.48	35.20	
५	१-७	सफैसलाई ड्रेसिङ्ग गर्ने कार्य , खाटो पुर्ने , उठेको माटो काट्ने , सतह मिलाउने आदि	Ps	रु.	10.12	8.80	

खण्ड ०८, संख्या ०४, मकवानपुर, श्रावण ३० गते, २०८१ साल

सिभिल (जेनरल/भवन निर्माण सम्बन्धि) कार्यको आईटम दर रेट सारांश-२०८१/०८२

सि.नं.	आईटम नं.	कामको विवरण	इकाई		आईटम दर (ठेक्काबाट)	आईटम दर (उपभोक्त गबाट)	८१/८ २ (ठेक्काबा ट)
		कार्य समेत (सर्भिसरोड आदि)					
६	१-८	माथिल्लो माटो खन्ने काम, निर्माण स्थलबाट बाहिर बोक्नी गर्ने समेत (माटोको तहको मोटाई १५-२० से.मी.)	व.मी.	रु.	161.92	140.80	
७	२५(१०)	साइट सफा गर्ने काम (भारपात काट्ने, रुख ढाल्ने र हटाउने काम ।	व.मी.	रु.	60.72	52.80	
कार्य समूह 'ख' :- माटो काट्ने र पुर्ने काम							
८	२-१	नरम प्रकारको बले र सिल्टी माटोमा सवै किसिमको खन्ने काम १० मीटर सम्म बोक्नी डिस्पोजल र १.५ मीटरसम्म लिफ्ट समेत	घ.मी.	रु.	729.65	634.48	
९	२-२	साह्रो प्रकारको बले, नरम मुरम ढुंगा (३० से.मी.सम्म) भिसेको माटो सवै किसिमको खन्ने काम १० मीटर बोक्नी डिस्पोजल र १.५ मीटरसम्म लिफ्ट समेत	घ.मी.	रु.	833.89	725.12	
१०	२ (२५)क	सामान्य माटोले पुर्ने काम १५, १५ से.मी. को तहमा फैलाउने,	घ.मी.	रु.	506.00	440.00	

खण्ड ०८, संख्या ०४, मकवानपुर, श्रावण ३० गते, २०८१ साल

सिभिल (जेनरल/भवन निर्माण सम्बन्धि) कार्यको आइटम दर रेट सारांश-२०८१/०८२

सि.नं.	आइटम नं.	कामको विवरण	इकाई		आइटम दर (ठेक्काबाट)	आइटम दर (उपभोक्त गबाट)	८१/८ २ (ठेक्काबा ट)
		पानी छर्ने र ज्यामिद्वारा कम्पैक्ट गर्ने काम समेत (१० मी. दूरीबाट ओसारने)					
११	२ (२५)क	सामान्य माटोले पुर्ने काम १५, १५ से.मी. को तहमा फैलाउने, पानी छर्ने र ज्यामिद्वारा कम्पैक्ट गर्ने काम समेत १० कि.मी. दूरीबाट ढुवानी गर्ने साथै माटोको मूल्य समेत	घ.मी.	रु.	582.21	506.27	
१२	२ (२५)ख	सामान्य माटोले पानी नछरिक्न पुर्ने काम	घ.मी.	रु.	253.00	220.00	
१३	२ - ३४	जग वा खाडलबाट पानी पम्प गर्ने ।	ली.	रु.	0.14	0.12	
१४	२ - ४२	वालुवा भर्ने, पानी छर्ने र ज्यामीद्वारा कम्पैक्ट गर्ने काम (१० मी.ढुवानी)	घ.मी.	रु.	2226.40	1936.0 0	
कार्य समूह 'ग' :- ईटाको काम							
१५	१५	भुईतल्लामा मेशिनद्वारा बनाइएको ईटा उपलब्ध गर्ने, सिमेन्ट मसला (१:३) तयार गरी गारो लगाउने काम ३० मीटरसम्म ढुवानी सहित	घ.मी.	रु.	17857.52	16998. 51	MM Chinese

खण्ड ०८, संख्या ०४, मकवानपुर, श्रावण ३० गते, २०८१ साल

सिभिल (जेनरल/भवन निर्माण सम्बन्धि) कार्यको आइटम दर रेट सारांश-२०८१/०८२

सि.नं.	आइटम नं.	कामको विवरण	इकाई		आइटम दर (ठेक्काबाट)	आइटम दर (उपभोक्त गबाट)	८१/८ २ (ठेक्काबा ट)
१६	१६	भुईतल्ला भन्दा माथी मेशिनद्वारा बनाइएको ईटा उपलब्ध गर्ने, सिमेन्ट मसला (१:३) तयार गरी गारो लगाउने काम ३० मीटरसम्म ढुवानी सहित	घ.मी.	रु.	18378.70	17451. 71	"
१७	१७	भुईतल्लामा मेशिनद्वारा बनाइएको ईटा उपलब्ध गर्ने, सिमेन्ट मसला (१:४) तयार गरी गारो लगाउने	घ.मी.	रु.	17409.02	16557. 81	
१८	१८	भुईतल्ला भन्दा माथी मेशिनद्वारा बनाइएको ईटा उपलब्ध गर्ने, सिमेन्ट मसला (१:४) तयार गरी गारो लगाउने काम ३० मीटरसम्म ढुवानी सहित	घ.मी.	रु.	17930.20	17011. 01	
१९	१९	भुईतल्लामा मेशिनद्वारा बनाइएको ईटा उपलब्ध गर्ने, सिमेन्ट मसला (१:५) तयार गरी गारो लगाउने काम ३० मीटरसम्म ढुवानी सहित	घ.मी.	रु.	17314.72	16458. 91	

खण्ड ०८, संख्या ०४, मकवानपुर, श्रावण ३० गते, २०८१ साल

सिभिल (जेनरल/भवन निर्माण सम्बन्धि) कार्यको आइटम दर रेट सारांश-२०८१/०८२

सि.नं.	आइटम नं.	कामको विवरण	इकाई		आइटम दर (ठेक्काबाट)	आइटम दर (उपभोक्त गबाट)	८१/८ २ (ठेक्काबा ट)
२०	२०	भुईतल्ला भन्दा माथी मेशिनद्वारा बनाइएको ईटा उपलब्ध गर्ने, सिमेन्ट मसला (१:५) तयार गरी गारो लगाउने काम ३० मीटरसम्म ढुवानी सहित	घ.मी.	रु.	17835.90	16912. 11	
२१	२१	भुईतल्लामा मेशिनद्वारा बनाइएको ईटा उपलब्ध गर्ने, सिमेन्ट मसला (१:६) तयार गरी गारो लगाउने	घ.मी.	रु.	17001.92	16153. 11	
२२	२२	भुईतल्ला भन्दा माथी मेशिनद्वारा बनाइएको ईटा उपलब्ध गर्ने, सिमेन्ट मसला (१:६) तयार गरी गारो लगाउने काम ३० मीटरसम्म ढुवानी सहित	घ.मी.	रु.	17523.10	16606. 31	
२३	२३	भुईतल्लामा चिमनी भट्टाको ईटा उपलब्ध गर्ने, सिमेन्ट मसला (१:३) तयार गरी गारो लगाउने काम ३० मीटरसम्म ढुवानी सहित	घ.मी.	रु.	16712.70	15873. 60	

खण्ड ०८, संख्या ०४, मकवानपुर, श्रावण ३० गते, २०८१ साल

सिभिल (जेनरल/भवन निर्माण सम्बन्धि) कार्यको आईटम दर रेट सारांश-२०८१/०८२

सि.नं.	आईटम नं.	कामको विवरण	इकाई		आईटम दर (ठेक्काबाट)	आईटम दर (उपभोक्त गबाट)	८१/८ २ (ठेक्काबा ट)
२४	२४	भुईतल्ला भन्दा माथी चिमनी भट्टाको ईटा उपलब्ध गर्ने, सिमेन्ट मसला (१:३) तयार गरी गारो लगाउने काम ३० मीटरसम्म ढुवानी सहित	घ.मी.	रु.	17233.88	16326.80	
२५	२५	भुईतल्लामा चिमनी भट्टाको ईटा उपलब्ध गर्ने, सिमेन्ट मसला (१:४) तयार गरी गारो लगाउने काम ३० मीटरसम्म ढुवानी सहित	घ.मी.	रु.	16278.00	15444.90	
२६	२६	भुईतल्ला भन्दा माथी चिमनी भट्टाको ईटा उपलब्ध गर्ने, सिमेन्ट मसला (१:४) तयार गरी गारो लगाउने काम ३० मीटरसम्म ढुवानी सहित	घ.मी.	रु.	16799.18	15898.10	
२७	२७	भुईतल्लामा चिमनी भट्टाको ईटा उपलब्ध गर्ने, सिमेन्ट मसला (१:६) तयार गरी गारो लगाउने काम ३० मीटरसम्म ढुवानी सहित	घ.मी.	रु.	15857.10	15028.20	

खण्ड ०८, संख्या ०४, मकवानपुर, श्रावण ३० गते, २०८१ साल

सिभिल (जेनरल/भवन निर्माण सम्बन्धि) कार्यको आईटम दर रेट सारांश-२०८१/०८२

सि.नं.	आईटम नं.	कामको विवरण	इकाई		आईटम दर (ठेक्काबाट)	आईटम दर (उपभोक्त गबाट)	८१/८ २ (ठेक्काबा ट)
२८	२८	भुईतल्ला भन्दा माथी चिमनी भट्टाको ईटा उपलब्ध गर्ने, सिमेन्ट मसला (१:६) तयार गरी गारो लगाउने काम ३० मीटरसम्म ढुवानी सहित	घ.मी.	रु.	16378.28	15481.40	
२९	२९	भुईतल्लामा चिमनी भट्टाको ईटा उपलब्ध गर्ने, माटोको मसला तयार गरी गारो लगाउने काम ३० मीटरसम्म ढुवानी सहित	घ.मी.	रु.	11819.09	11238.43	
३०	३०	भुईतल्ला भन्दा माथी चिमनी भट्टाको ईटा उपलब्ध गर्ने, माटोको मसला तयार गरी गारो लगाउने काम ३० मीटरसम्म ढुवानी सहित	घ.मी.	रु.	12340.27	11691.63	
कार्य समूह 'घ' :- ढुङ्गाको काम							
३१	३१	ढुंगाको (रबुल) गारोको काम साह्रो ब्लकस्टोन उपलब्ध गर्ने, सिमेन्ट मसला १:३ तयार गरी गारो लग काम पुरा १० मीटरसम्म ढुवानी सहित	घ.मी.	रु.	13999.53	12501.36	

खण्ड ०८, संख्या ०४, मकवानपुर, श्रावण ३० गते, २०८१ साल

सिभिल (जेनरल/भवन निर्माण सम्बन्धि) कार्यको आईटम दर रेट सारांश-२०८१/०८२

सि.नं.	आईटम नं.	कामको विवरण	इकाई		आईटम दर (ठेक्काबाट)	आईटम दर (उपभोक्त गबाट)	८१/८ २ (ठेक्काबा ट)
३२	३२	ढुंगाको (रबुल) गारोको काम साह्रो ब्लकस्टोन उपलब्ध गर्ने, सिमेन्ट मसला १:४ तयार गरी गारो लगाउने काम पुरा १० मीटरसम्म ढुवानी सहित	घ.मी.	रु.	13503.88	12011.21	
३३	३३	ढुंगाको (रबुल) गारोको काम साह्रो ब्लकस्टोन उपलब्ध गर्ने, सिमेन्ट मसला १:६ तयार गरी गारो लगाउने काम पुरा १० मीटरसम्म ढुवानी सहित	घ.मी.	रु.	12752.93	11268.64	
३४	३४	ढुंगाको (रबुल) गारोको काम साह्रो ब्लकस्टोन उपलब्ध गर्ने, सुख्खा गारो लगाउने काम पुरा ३० मीटरसम्म ढुवानी सहित	घ.मी.	रु.	6802.25	5915.00	
३५	३५	ढुंगाको (रबुल) गारोको काम साह्रो ब्लकस्टोन उपलब्ध गर्ने, माटोको मसला तयार गरी गारो लगाउने काम पुरा ३० मीटरसम्म ढुवानी सहित	घ.मी.	रु.	7081.92	6158.19	

खण्ड ०८, संख्या ०४, मकवानपुर, श्रावण ३० गते, २०८१ साल

सिभिल (जेनरल/भवन निर्माण सम्बन्धि) कार्यको आईटम दर रेट सारांश-२०८१/०८२

सि.नं.	आईटम नं.	कामको विवरण	इकाई		आईटम दर (ठेक्काबाट)	आईटम दर (उपभोक्त गबाट)	८१/८ २ (ठेक्काबा ट)
३६	३६	ढुंगाको (रबुल) गारो आर्च वा तेर्सो सतहमा लगाउने काम ब्लक स्टोन उपलब्ध गरी सिमेन्ट मसला १:३ तयार गरी गारो लगाउने ब्लक स्टोन उपलब्ध गरी सिमेन्ट मसला १:३ तयार गरी गारो लगाउने	घ.मी.	रु.	15085.70	13445.86	
३७	३७	ढुंगाको (रबुल) गारो आर्च वा तेर्सो सतहमा लगाउने काम ब्लक स्टोन उपलब्ध गरी सिमेन्ट मसला १:४ तयार गरी गारो काम पुरा ३० मीटरसम्म ढुवानी सहित	घ.मी.	रु.	14603.85	12967.71	
३८	३८	ढुंगाको (रबुल) गारो आर्च वा तेर्सो सतहमा लगाउने काम ब्लक स्टोन उपलब्ध गरी सिमेन्ट मसला १:६ तयार गरी गारो लगाउने काम पुरा ३० मीटरसम्म ढुवानी सहित	घ.मी.	रु.	11815.10	10453.14	
३९	४०	जगको खाडलमा ढुंगा भर्ने र लेभल गर्ने काम ३० मीटरसम्म ढुवानी	घ.मी.	रु.	3036.00	2640.00	

खण्ड ०८, संख्या ०४, मकवानपुर, श्रावण ३० गते, २०८१ साल

सिभिल (जेनरल/भवन निर्माण सम्बन्धि) कार्यको आइटम दर रेट सारांश-२०८१/०८२

सि.नं.	आइटम नं.	कामको विवरण	इकाई		आइटम दर (ठेक्काबाट)	आइटम दर (उपभोक्त गबाट)	८१/८ २ (ठेक्काबा ट)
कार्य समूह 'ड' :- सिमेन्ट कंक्रीटको काम							
४०	४२	जग (भित्ता पर्खाल)मा सिमेन्ट कंक्रीट गर्ने काम मालसामान उपलब्ध गर्ने ३० मीटरसम्म ढुवानी सहित (पि.सी.सी. १:४:८)	घ.मी.	रु.	9988.50	8972.9 5	
४१	४३	जग (भित्ता पर्खाल)मा सिमेन्ट कंक्रीट गर्ने काम मालसामान उपलब्ध गर्ने ३० मीटरसम्म ढुवानी सहित (पि.सी.सी. १:३:६)	घ.मी.	रु.	10736.00	9707.4 5	
४२	४४	जग (भित्ता पर्खाल)मा सिमेन्ट कंक्रीट गर्ने काम मालसामान उपलब्ध गर्ने ३० मीटरसम्म ढुवानी सहित (पि.सी.सी. १:२:४)	घ.मी.		12190.35	11141. 10	
४३	४५	जग (भित्ता पर्खाल)मा सिमेन्ट कंक्रीट गर्ने काम सिलिका एडमिक्चर सहित मालसामान उपलब्ध गर्ने ३० मीटरसम्म ढुवानी सहित (पि.सी.सी. १:२:४)	घ.मी.	रु.	18630.35	17469. 10	

खण्ड ०८, संख्या ०४, मकवानपुर, श्रावण ३० गते, २०८१ साल

सिभिल (जेनरल/भवन निर्माण सम्बन्धि) कार्यको आईटम दर रेट सारांश-२०८१/०८२

सि.नं.	आईटम नं.	कामको विवरण	इकाई		आईटम दर (ठेक्काबाट)	आईटम दर (उपभोक्त गबाट)	८१/८ २ (ठेक्काबा ट)
४४	४६	सुपर स्टक्चर, डेक स्लेब विमहरुमा सिमेन्ट कंक्रीट गर्ने काम मालसामान उपलब्ध गर्ने ३० मीटरसम्म ढुवानी समेत (पि.सी.सी. १:२:४)	घ.मी.	रु.	15092.08	13664.35	
४५	४७	सुपर स्टक्चर, डेक स्लेब विमहरुमा सिलिका एड्मिक्चर सहित सिमेन्ट कंक्रीट गर्ने काम मालसामान उपलब्ध गर्ने ३० मीटरसम्म ढुवानी समेत (पि.सी.सी. १:१.५:३)	घ.मी.	रु.	24481.89	21964.60	
४६	४८	सुपर स्टक्चर, डेक स्लेब विमहरुमा सिमेन्ट कंक्रीट गर्ने काम मालसामान उपलब्ध गर्ने ३० मीटरसम्म ढुवानी समेत (पि.सी.सी. १:१.५:३)	घ.मी.	रु.	16431.89	14964.60	
४७	४९	सुपर स्टक्चर, डेक स्लेब विमहरुमा सिलिका एड्मिक्चर सहित सिमेन्ट कंक्रीट गर्ने काम मालसामान उपलब्ध गर्ने ३० मीटरसम्म ढुवानी	घ.मी.	रु.	31827.98	28707.40	

खण्ड ०८, संख्या ०४, मकवानपुर, श्रावण ३० गते, २०८१ साल

सिभिल (जेनरल/भवन निर्माण सम्बन्धि) कार्यको आइटम दर रेट सारांश-२०८१/०८२

सि.नं.	आइटम नं.	कामको विवरण	इकाई		आइटम दर (ठेक्काबाट)	आइटम दर (उपभोक्त गबाट)	८१/८ २ (ठेक्काबा ट)
		समेत (पि.सी.सी. १:१:२)					
४८	५०	सुपर स्ट्रक्चर, डेक स्लेब विमहरुमा सिमेन्ट कंक्रीट गर्ने काम मालसामान उपलब्ध गर्ने ३० मीटरसम्म हुवानी समेत (पि.सी.सी. १:१:२)	घ.मी.	रु.	19551.73	18032. 40	
४९	५१	मेशिनको प्रयोग गरी जग भित्ता पर्खालमा सिमेन्ट कंक्रीट गर्ने काम (१:३:६)	घ.मी.	रु.	11069.45	10053. 70	
५०	५२	मेशिनको प्रयोग गरी जग भित्ता पर्खालमा सिमेन्ट कंक्रीट गर्ने काम (१:२:४)	घ.मी.	रु.	12515.17	11479. 85	
५१	५३	मेशिनको प्रयोग गरी सुपर स्ट्रक्चरमा सिमेन्ट कंक्रीट गर्ने काम (१:१:५:३)	घ.मी.	रु.	13711.12	12655. 00	
५२	५४	मेशिनको प्रयोग गरी सुपर स्ट्रक्चरमा सिमेन्ट कंक्रीट गर्ने काम (१:१:२)	घ.मी.	रु.	16828.19	15720. 40	
५३	५५	कंक्रीट होलो ब्लकको गारो सिमेन्ट, बालुवा (१:४) मा लगाउने काम	व.मी.	रु.	1506.19		

खण्ड ०८, संख्या ०४, मकवानपुर, श्रावण ३० गते, २०८१ साल

सिभिल (जेनरल/भवन निर्माण सम्बन्धि) कार्यको आईटम दर रेट सारांश-२०८१/०८२

सि.नं.	आईटम नं.	कामको विवरण	इकाई		आईटम दर (ठेक्काबाट)	आईटम दर (उपभोक्त गबाट)	८१/८ २ (ठेक्काबा ट)
कार्य समूह 'च' :- फर्माको काम							
५४	५०	काठमा फर्मा बनाउने काम, मालसामानको उपलब्धि, छनौट गर्ने, नक्सा अनुसार फर्मा राख्ने किला र अन्तर लगाउने फर्मा भित्रको, हटाउने ३० मिटरसम्म ढुवानी सहित फर्श र स्लेव जस्ता काम	व.मी.	रु.	813.32	707.23	
५५	५१	कोलम (पोष्ट) फर्मा लगाउनलाई खडा गर्ने, काम मिलाउने, किला लगाउने भत्काउने र हटाउने र ३० मिटरसम्म ढुवानी गर्ने आदि समेत	व.मी.	रु.	1514.88	1317.28	
५६	५२	फलामको पाइप (Prop), प्लाइवोर्ड प्रयोग गरी फर्श र स्लावको लागि फर्मा बनाउने काम ।	व.मी.	रु.	844.93	759.11	
५७	५३	विमको लागि १२ मी.मी प्लाईको फर्मा बनाउने काम,मालसामानको उपलब्धि, छनौट गर्ने, नक्सा अनुसार फर्मा राख्ने	व.मी.	रु.	1279.18	1144.44	

खण्ड ०८, संख्या ०४, मकवानपुर, श्रावण ३० गते, २०८१ साल

सिभिल (जेनरल/भवन निर्माण सम्बन्धि) कार्यको आईटम दर रेट सारांश-२०८१/०८२

सि.नं.	आईटम नं.	कामको विवरण	इकाई		आईटम दर (ठेक्काबाट)	आईटम दर (उपभोक्त गबाट)	८१/८ २ (ठेक्काबा ट)
५८	५४	१२ मी.मी प्लाई बोर्डको फर्मा कोलम (पोष्ट)मा लगाउने, खडा गर्ने, काम मिलाउने, किला लगाउने भत्काउने र हटाउने र ३० मिटरसम्म ढुवानी गर्ने आदि समेत फर्माको काम २ मि. सम्म गोलाईको कोलम ।	व.मी.	रु.	1611.93	1432.15	
५९	५५	टेन्चको काममा आवश्यक पर्ने खुला किसिमको काठको काम उपलब्धि तथा जडान समेत १.५ मी. देखि ३ मी. भन्दा कम गहिराईमा ।	व.मी.	रु.	388.82	338.11	
६०	५६	टेन्चको काममा आवश्यक पर्ने खुला किसिमको काठको काम उपलब्धि तथा जडान समेत ३ मी. भन्दा बढी गहिराईमा ।	व.मी.	रु.	403.23	350.63	
६१	५७	किला लगाउने आईलिङ्ग भत्काउने हटाउने ३० मी. सम्म ढुवानी सहित वीमको उचाई ०.३० मी. सम्म ।	व.मी.	रु.	1471.14	1282.47	

खण्ड ०८, संख्या ०४, मकवानपुर, श्रावण ३० गते, २०८१ साल

सिभिल (जेनरल/भवन निर्माण सम्बन्धि) कार्यको आईटम दर रेट सारांश-२०८१/०८२

सि.नं.	आईटम नं.	कामको विवरण	इकाई		आईटम दर (ठेक्काबाट)	आईटम दर (उपभोक्त गबाट)	८१/८ २ (ठेक्काबाट)
६२	५८	किला लगाउने आईलिङ्ग भत्काउने हटाउने ३० मी. सम्म ढुवानी सहित वीमको उचाई ०.३० मी. ~) .८०मि.मि. सम्म ।	व.मी.	रु.	1087.49	948.86	
कार्य समूह 'छ' :- छानाको काम							
६३	५९/९-१	मालसामान उपलब्ध गरी ०.५० मी.मी. (२६ गेज हेभी) बाक्लो सी.जी.आई. शीट (प्लेन जस्तापाताको) छाना छाउने काम पुरा ।	व.मी.	रु.	1040.72	991.38	
६४	६०/९-२	मालसामान उपलब्ध गरी ०.४९ मी.मी. (२६ गेज मेडियम) बाक्लो सी.जी.आई. शीट (प्लेन जस्तापाताको) छाना छाउने काम पुरा ।	व.मी.	रु.	981.74	933.42	
६५	६१/९-३	मालसामान उपलब्ध गरी ०.३५ मी.मी. (२६ गेज लाइट) बाक्लो सी.जी.आई. शीट (प्लेन जस्तापाताको) छाना छाउने काम पुरा ।	व.मी.	रु.	949.99	902.22	

खण्ड ०८, संख्या ०४, मकवानपुर, श्रावण ३० गते, २०८१ साल

सिभिल (जेनरल/भवन निर्माण सम्बन्धि) कार्यको आइटम दर रेट सारांश-२०८१/०८२

सि.नं.	आइटम नं.	कामको विवरण	इकाई		आइटम दर (ठेक्काबाट)	आइटम दर (उपभोक्त गबाट)	८१/८ २ (ठेक्काबा ट)
६६	६२	मालसामान उपलब्ध गरी २६ गेज लाइट(०.३५ मि.मि.) प्लेन शीटको धुरी बनाई जडान गर्ने काम पुरा ।	र.मी.	रु.	895.46	814.76	
६७	६४/९-१	मालसामान उपलब्ध गरी ०.५० मी.मी. (२६ गेज हेभी) बाक्लो सी.जी.आई. शीट (रंगिन जस्तापाताको) छाना छाउने काम पुरा ।	व.मी.	रु.	1231.26	1178.60	
६८	६५/९-१	मालसामान उपलब्ध गरी ०.४१ मी.मी. (२६ गेज मेडियम) बाक्लो सी.जी.आई. शीट (रंगिन जस्तापाताको) छाना छाउने काम पुरा ।	व.मी.	रु.	1158.68	1107.28	
६९	६५/९-१	मालसामान उपलब्ध गरी ०.३५ मी.मी. (२६ गेज लाइट) बाक्लो सी.जी.आई. शीट (रंगिन जस्तापाताको) छाना छाउने काम पुरा ।	व.मी.	रु.	1113.31	1062.70	
७०	६७	मालसामान उपलब्ध गरी २६ गेज लाइट(०.३५ मि.मि.) रंगिन	र.मी.	रु.	799.30	720.27	

खण्ड ०८, संख्या ०४, मकवानपुर, श्रावण ३० गते, २०८१ साल

सिभिल (जेनरल/भवन निर्माण सम्बन्धि) कार्यको आईटम दर रेट सारांश-२०८१/०८२

सि.नं.	आईटम नं.	कामको विवरण	इकाई		आईटम दर (ठेक्काबाट)	आईटम दर (उपभोक्त गबाट)	८१/८ २ (ठेक्काबा ट)
		शीटको धुरी बनाई जडान गर्ने काम पुरा ।					
कार्य समूह 'ज' :- काठको काम							
७१	७१/९- १०	मालसामान उपलब्ध गरी २० मी.मी. मोटाईको साल काठको सिलिङ लगाउने काम ४० ह २० मी.मी. विडिंग ज्वाइन्टमा लगाउने समेत ।	व.मी.	रु.	4543.38	3953.3 6	
७२	७२/१०- १	सालकाठको चौकस बनाई जोड्ने काम । (ढोका नाप ९०० X २१०० मी.मी. काठको साईज १०० X ७५ मी.मी.)	घ.मी.	रु.	268010.84	23323 0.59	35459. 540
७३	७४/१०- २	३८ मी.मी. बाक्लो चिरान अग्राख काठको फ्रेम हाली फेन्सी डिलाखापा बनाई जडान गर्ने । (खापाको नाप १.०७ मी.ह १.९८२ मी.. २.११४ व. मी.)	व.मी.	रु.	15491.38	13554. 40	5284.6 1
७४	७५/१०- २	३८ मी.मी. बाक्लो चिरान अग्राख काठको फ्रेम हाली साधारण डिलाखापा बनाई जडान गर्ने । (खापाको	व.मी.	रु.	15475.06	13538. 36	5268.5 7

खण्ड ०८, संख्या ०४, मकवानपुर, श्रावण ३० गते, २०८१ साल

सिभिल (जेनरल/भवन निर्माण सम्बन्धि) कार्यको आइटम दर रेट सारांश-२०८१/०८२

सि.नं.	आइटम नं.	कामको विवरण	इकाई		आइटम दर (ठेक्काबाट)	आइटम दर (उपभोक्त गबाट)	८१/८ २ (ठेक्काबा ट)
		नाप १.०७ मी.ह १.९८२ मी.. २.११४ व. मी.)					
७५	७६/१०- ३	३८ X ७५ मी.मी.चिरान साल काठको फ्रेम बनाई ३ मी.मी. ऐना खापा बनाई जडान गर्ने ।	व.मी.	रु.	10830.04	9484.5 4	4659.9 8
७६	७७/१०- ४	३८ X ७५ मी.मी.चिरान साल काठको फ्रेम बनाई ४ मी.मी. साधारण ऐना खापा बनाई जडान गर्ने ।	व.मी.	रु.	10830.04	9484.5 4	4570.3 4
७७	७८/१०- ४	३८ X ७५ मी.मी.चिरान साल काठको फ्रेम बनाई ४ मी.मी. फेन्स ऐना खापा बनाई जडान गर्ने ।	व.मी.	रु.	10824.88	9479.4 7	4565.2 7
७८	७९/१०- ५	३८ X ७५ मी.मी. साल काठको फ्रेम बनाई ५.० मी.मी. ऐना खापा बनाई जडान गर्ने ।	व.मी.	रु.	10957.39	9609.6 7	4684.8
७९	८०/१० -६	३८ X ७५ मी.मी. साल काठको फ्रेम बनाई ६ मी.मी. ऐना खापा बनाई जडान गर्ने ।	व.मी.	रु.	10957.39	9609.6 7	4692.4 1

खण्ड ०८, संख्या ०४, मकवानपुर, श्रावण ३० गते, २०८१ साल

सिभिल (जेनरल/भवन निर्माण सम्बन्धि) कार्यको आईटम दर रेट सारांश-२०८१/०८२

सि.नं.	आईटम नं.	कामको विवरण	इकाई		आईटम दर (ठेक्काबाट)	आईटम दर (उपभोक्त गबाट)	८१/८ २ (ठेक्काबा ट)
८०	८१/१०- ७	३८ मी.मी. बाक्लो अग्राख काठको फ्रेममा ४ मी.मी. कमर्सियल प्लाईउड दुवै तर्फ ठोकी फ्लस खापा बनाई जोड्ने ।	व.मी.	रु.	8786.58	7774.6 0	4179.1 9
८१	८२/१०- ७	३८ मी.मी. बाक्लो अग्राख काठको फ्रेममा ६ मी.मी. वाटरपुफ प्लाईउड एकतर्फ र अर्कोतर्फ ४ मी.मी. कमर्सियल प्लाईउड ठोकी फ्लस खापा बनाई जोड्ने ।	व.मी.	रु.	9307.66	8286.6 1	4670.2 8
८२	८३/१०- ८	३८ मी.मी. बाक्लो अग्राख काठको फ्रेममा ४ मी.मी. ठीक प्लाईउड दुवै तर्फ ठोकी फ्लस खापा बनाई जोड्ने ।	व.मी.	रु.	9376.16	8353.9 3	
८३	८४/१० -९	३८ मी.मी. बाक्लो अग्राख काठको फ्रेममा २८ गेज जी.आई. प्लेन शीट दुवै पट्टी खापा बनाई जोड्ने ।	व.मी.	रु.	24464.60	23179. 96	
८४	८५/१०- १०	३८ मी.मी. बाक्लो अग्राख काठको फ्रेममा जी.आई. मस्क्वीटो पुफ वायर मेश वर्फी जाली	व.मी.	रु.	7320.77	6567.0 1	

खण्ड ०८, संख्या ०४, मकवानपुर, श्रावण ३० गते, २०८१ साल

सिभिल (जेनरल/भवन निर्माण सम्बन्धि) कार्यको आईटम दर रेट सारांश-२०८१/०८२

सि.नं.	आईटम नं.	कामको विवरण	इकाई		आईटम दर (ठेक्काबाट)	आईटम दर (उपभोक्त गबाट)	८१/८ २ (ठेक्काबा ट)
		सहित ठोकी खापा बनाई जोड्ने ।					
८५	८६/१०-१०	काठको फ्रेममा मस्क्वीटो प्रुफ जाली लिफ्टिद्वारा जडान गर्ने कार्य ।	व.मी.	रु.	495.08	476.53	
८६	८७/१०-१०	३८ मी.मी. बाक्लो कु काठको फ्रेममा जी.आई. मस्क्वीटो प्रुफ वायर मेश जाली सहित ठोकी खापा बनाई जोड्ने ।	व.मी.	रु.	5331.87	4794.53	
८७	८८/१०-११	चौकोसमा ३ मी.मी. मोटाईको ऐना काठको लिफ्टी लगाई जोड्ने ।	व.मी.	रु.	841.79	817.21	
८८	८९/१०-११	चौकोसमा दुबै तर्फ २८ गेजको प्लेनसिट काठको लिफ्टी लगाई ठोक्ने कामे ।	व.मी.	रु.	8003.98	7854.85	
८९	९०/१०-११ ख	चौकोसमा ४ मी.मी. मोटाईको ऐना काठको लिफ्टी लगाई जोड्ने ।	व.मी.	रु.	841.79	817.21	
९०	९१/१०-११ ग	चौकोसमा ५ मी.मी. मोटाईको ऐना काठको लिफ्टी लगाई जोड्ने ।	व.मी.	रु.	1114.12	1084.81	
९१	९२/१०-११ घ	चौकोसमा ६ मी.मी. मोटाईको ऐना काठको लिफ्टी लगाई जोड्ने ।	व.मी.	रु.	1114.12	1084.81	

खण्ड ०८, संख्या ०४, मकवानपुर, श्रावण ३० गते, २०८१ साल

सिभिल (जेनरल/भवन निर्माण सम्बन्धि) कार्यको आईटम दर रेट सारांश-२०८१/०८२

सि.नं.	आईटम नं.	कामको विवरण	इकाई		आईटम दर (ठेक्काबाट)	आईटम दर (उपभोक्त गबाट)	८१/८ २ (ठेक्काबा ट)
९२	९३/१०- १२	चौकोसमा ४ मी.मी. कर्मसियल प्लाईउड काठको लिष्टी लगाई जोड्ने ।	व.मी.	रु.	459.80	441.87	
९३	९४/१०- १४क	३८ X ७५ मी.मी. साईजको अग्राख काठको ०.६९ X ०.९१५ मी. को कोठा बनाई दुवैतर्फ ४ मी.मी. कर्मसियल प्लाईउड लगाई जोर्नीमा काठको लिष्टी ठोकी कठवार लगाउने ।	व.मी.	रु.	3532.21	3144.7 8	
९४	९५/१०- १४ख	३८ X ७५ मी.मी. साईजको अग्राख काठको ०.६९ X ०.९१५ मी. को कोठा बनाई दुवैतर्फ १२ मी.मी. कर्मसियल प्लाईउड लगाई जोर्नीमा काठको लिष्टी ठोकी कठवार लगाउने ।	व.मी.	रु.	4419.06	4016.2 0	
९५	९६/१०- १४ख	३८ X ७५ मी.मी. साईजको अग्राख काठको ०.६९ X ०.९१५ मी. को कोठा बनाई दुवैतर्फ जि. आइ. प्लेनसिट लगाई	व.मी.	रु.	19464.76	18800. 23	

खण्ड ०८, संख्या ०४, मकवानपुर, श्रावण ३० गते, २०८१ साल

सिभिल (जेनरल/भवन निर्माण सम्बन्धि) कार्यको आईटम दर रेट सारांश-२०८१/०८२

सि.नं.	आईटम नं.	कामको विवरण	इकाई		आईटम दर (ठेक्काबाट)	आईटम दर (उपभोक्त गबाट)	८१/८ २ (ठेक्काबा ट)
		जोर्नीमा काठको लिष्टी ठोकी ढोका लगाउने ।					
९६	९७/१०- १२क	१२ मी.मी. मोटाई भएको पार्टीशन बोर्ड एक साइड टिक भएको जडान गर्ने कार्य ।	व.मी.	रु.	1266.62	1234.6 6	
९७	९८/१०- १२क	हार्डबोर्ड तथा अन्य पार्टीशनमा ४ मी.मी. टीक प्लाइउड लेमिनेशन गरी जोड्ने काम एकतर्फ मात्र ।	व.मी.	रु.	789.05	765.40	
९८	९९/१०- १६क	५० X ७५ मी.मी. साईजको अग्राख काठको ६०० X ९०० मी. मी. को कोठा बनाई विभिन्न किसिमको फल्स सिलिङ्ग ठोक्ने ४ मी.मी. कमर्सियल प्लाईउड	व.मी.	रु.	3777.84	3323.5 6	
९९	१००/१० -१६क	५० X ७५ मी.मी. साईजको कु काठको ६०० X ९०० मी. मी. को कोठा बनाई विभिन्न किसिमको फल्स सिलिङ्ग ठोक्ने ४ मी.मी. कमर्सियल प्लाईउड	व.मी.	रु.	2021.19	1796.0 3	

खण्ड ०८, संख्या ०४, मकवानपुर, श्रावण ३० गते, २०८१ साल

सिभिल (जेनरल/भवन निर्माण सम्बन्धि) कार्यको आइटम दर रेट सारांश-२०८१/०८२

सि.नं.	आइटम नं.	कामको विवरण	इकाई		आइटम दर (ठेक्काबाट)	आइटम दर (उपभोक्त गबाट)	८१/८ २ (ठेक्काबा ट)
१००	१०१/१० -१६क	५० X ७५ मी.मी. साईजको सल्लो कु काठको ६०० X ९०० मी. मी. को कोठा बनाई विभिन्न किसिमको फल्स सिलिङ्ग ठोक्ने ६ मी.मी. कर्मसियल प्लाईउड	व.मी.	रु.	2190.73	1962.6 2	
१०१	१०२/१० -१७	अग्राख काठको वीम लिनटल आदि बनाई जोड्ने ।	घ.मी.	रु.	232706.85	20236 0.21	
१०२	१०३/१० -१७	कु काठको वीम लिनटल आदि बनाई जोड्ने ।	घ.मी.	रु.	86869.39	75545. 04	
१०३	१०४/१ ०-१९	२५ मी.मी. अग्राख काठको ईभ्स (मुठल) बनाई जोड्ने ।	व.मी.	रु.	5632.86	4898.9 2	
१०४	१०५/१० -२१	प्वाल खोपी ढण्डी जडान गर्ने काम ।	के.जी.	रु.	165.83	157.58	
१०५	१०५.१	सनमाईका लेमिनेशन काम	व.मी.	रु.	611.35	590.79	
१०६	१०५.२	फोरमाईका लेमिनेशन काम	व.मी.	रु.	923.19	897.20	
कार्य समूह 'भ' :- फ्लोरिङ्गको काम							
१०७	१०६/११ -१ ख	३८ मी.मी. (१½") बाक्लो सिमेन्ट कंक्रीट (१:२:४) फ्लोर ढलान	व.मी.	रु.	655.69	592.13	

खण्ड ०८, संख्या ०४, मकवानपुर, श्रावण ३० गते, २०८१ साल

सिभिल (जेनरल/भवन निर्माण सम्बन्धि) कार्यको आइटम दर रेट सारांश-२०८१/०८२

सि.नं.	आइटम नं.	कामको विवरण	इकाई		आइटम दर (ठेक्काबाट)	आइटम दर (उपभोक्त गबाट)	८१/८ २ (ठेक्काबा ट)
		गरी सिमेन्ट घोटी तयार गर्ने ।					
१०८	१०७/१ १-१ ग	५० मी.मी. (२") बाक्लो सिमेन्ट कंक्रीट (१:२:४) फ्लोर ढलान गरी सिमेन्ट घोटी तयार गर्ने ।	व.मी.	रु.	790.70	716.29	
१०९	१०८/१ १-१ घ	७५ मी.मी. (३") बाक्लो सिमेन्ट कंक्रीट (१:२:४) फ्लोर ढलान गरी सिमेन्ट घोटी तयार गर्ने ।	व.मी.	रु.	1029.99	939.58	
११०	१०९/१ १-२	२५ मी.मी. बाक्लो मोजायक फ्लोरिङ्ग २० मी.मी. (१:२:४) सिमेन्ट कंक्रीट गरी त्यस माथि ५ मी.मी. बाक्लो १:१ भागमा सेतो सिमेन्ट र मार्बल चिप्स लगाई घोट्ने र पालिश समेत गर्ने काम ।	व.मी.	रु.	2709.41	2435.8 4	
१११	११०/११ -३	२५ मी.मी. बाक्लो मोजायक फ्लोरिङ्ग १९ मी.मी. सिमेन्ट प्लाष्टर १:२ भागमा गरी त्यस माथि ६ मी.मी. मार्बल चिप्स सेतो सिमेन्ट १:१ भागमा लगाई घोट्ने र पालिश गर्ने ।	व.मी.	रु.	4885.29	4332.0 0	

खण्ड ०८, संख्या ०४, मकवानपुर, श्रावण ३० गते, २०८१ साल

सिभिल (जेनरल/भवन निर्माण सम्बन्धि) कार्यको आईटम दर रेट सारांश-२०८१/०८२

सि.नं.	आईटम नं.	कामको विवरण	इकाई		आईटम दर (ठेक्काबाट)	आईटम दर (उपभोक्त गबाट)	८१/८ २ (ठेक्काबा ट)
११२	१११/११ -४	२० मी.मी. बाक्लो मोजायक फ्लोरिङ गर्ने १२.५ मी.मी. सिमेन्ट प्लाष्टर १:२ भागमा लगाई त्यस माथि ६ मी.मी. सेतो सिमेन्ट मार्बल चिप्स १:१ भागमा लगाई घोट्ने र पालिश गर्ने ।	व.मी.	रु.	5032.13	4476.9 6	
११३	११२/११ -५	२० मी.मी. टेराजो टाईल २० मी.मी. बाक्लो १:४ भागमा सिमेन्ट बालुवा मसलामा लगाई घोट्ने र पालिश गर्ने ।	व.मी.	रु.	4276.85	3869.6 5	
११४	११३/११ -६	१५ मी.मी. बाक्लो मार्बल (६०० X ६०० मी.मी.) २० मी.मी. बाक्लो १:२ भागको सिमेन्ट मसलामा छापी घोट्ने र पालिश समेत गर्ने ।	व.मी.	रु.	5324.01	4951.7 9	
११५	११४/१ १-७	पोरसिलिन ग्लेज्ड टाईल १:४ सिमेन्ट बालुवामा छापे काम ।	व.मी.	रु.	3387.63	3074.6 0	
११६	११५/११ -७	स्पार्टिक नन् ग्लेज्ड टाईल १:४ सिमेन्ट बालुवामा छापे काम ।	व.मी.	रु.	3512.87	3197.6 6	
११७	१२०/१ १-१२	चेप्टो ईटा (१:६) सिमेन्ट बालुवामा छापि	व.मी.	रु.	1545.26	1442.9 7	

खण्ड ०८, संख्या ०४, मकवानपुर, श्रावण ३० गते, २०८१ साल

सिभिल (जेनरल/भवन निर्माण सम्बन्धि) कार्यको आईटम दर रेट सारांश-२०८१/०८२

सि.नं.	आईटम नं.	कामको विवरण	इकाई		आईटम दर (ठेक्काबाट)	आईटम दर (उपभोक्त गबाट)	८१/८ २ (ठेक्काबा ट)
		१:२ सिमेन्ट, बालुवा जोर्नीमा टिप्कार गर्ने काम ।					
११८	१२१/११-१३	ठाडो ईटा (१:६) सिमेन्ट बालुवामा छापी १:२ सिमेन्ट, बालुवा जोर्नीमा टिप्कार गर्ने काम ।	व.मी.	रु.	1900.68	1823.36	
११९	१२२/११-१३	ठाडो फायर ईटा (१:६) सिमेन्ट बालुवामा छापी १:२ सिमेन्ट, बालुवा जोर्नीमा टिप्कार गर्ने काम ।	व.मी.	रु.	7138.59	6970.18	
१२०	१२३/११-१५क	सुख्खा ईटा च्याप्टो छाप्ने काम ।	व.मी.	रु.	1011.13	963.33	
१२१	१२४/११-१५ख	सुख्खा ईटा ठाडो छाप्ने काम ।	व.मी.	रु.	1891.40	1794.85	
१२२	१२५/११-१६	सुख्खा ढुंगा छाप्ने काम ।	घ.मी.	रु.	7276.05	6327.00	
१२३	१२६/११-१७	१२५ मी.मी. बाक्लो ठाडो ईटा सोलिङ्ग गरी जोर्नीमा बालुवाले भर्ने तथा जोर्नीको माथि तल्लो भागमा १:३ सिमेन्ट बालुवाको मसलाको फ्लश टिप्कार गर्ने काम ।	व.मी.	रु.	1641.97	1535.28	
१२४	१२७/११-१८	४६ से.मी.X ४६ से.मी. ढुंगा छापेकोमा	व.मी.	रु.	125.43	109.77	

खण्ड ०८, संख्या ०४, मकवानपुर, श्रावण ३० गते, २०८१ साल

सिभिल (जेनरल/भवन निर्माण सम्बन्धि) कार्यको आईटम दर रेट सारांश-२०८१/०८२

सि.नं.	आईटम नं.	कामको विवरण	इकाई		आईटम दर (ठेक्काबाट)	आईटम दर (उपभोक्त गबाट)	८१/८ २ (ठेक्काबा ट)
		सिमेन्ट बालुवा १:१ ले टिप्कार गर्ने ।					
१२५	१२८/१ १-१९क	फ्लोरिङ्ग कार्यका लागि बालुवाले भर्ने काम ।	घ.मी.	रु.	2175.80	1892.0 0	
१२६	१२९/११ -२०ख	१५ मी.मी. देखि १५० मी.मी. टुक्रा ईटाले भर्ने काम ।	घ.मी.	रु.	4752.35	4555.3 0	
१२७	१३०/११ -२०	३ मी.मी. मोटाई मसीनो सिमेन्ट घोदने काम ।	व.मी.	रु.	317.00	284.65	
१२८	१३१/११ -२०	भित्ता एवं सिलिङ्गमा प्लेन प्लास्टर अफ पेरिस गर्ने कार्य ।	व.मी.	रु.	372.07	338.75	
१२९	१३२/११ -२१	५० मी.मी. X ७५ मी.मी. अग्राखको फ्रेम ६०० मी.मी. X ६०० मी.मी. मा हाली २५ मी.मी. बाक्लो अग्राखको काठको फ्लेक छान्ने काम ।	व.मी.	रु.	9266.68	8060.5 6	
१३०		५० मी.मी. मोटो हेभी ड्यूटी इन्टरलकिंग कंक्रीटब्लक बिछ्याउने काम	व.मी.	रु.	1994.47	1820.4 9	
१३१		६० मी.मी. मोटो हेभी ड्यूटी इन्टरलकिंग कंक्रीटब्लक बिछ्याउने काम	व.मी.	रु.	2063.16	1887.9 1	
कार्य समूह 'अ' :- प्लास्टरको काम							

खण्ड ०८, संख्या ०४, मकवानपुर, श्रावण ३० गते, २०८१ साल

सिभिल (जेनरल/भवन निर्माण सम्बन्धि) कार्यको आईटम दर रेट सारांश-२०८१/०८२

सि.नं.	आईटम नं.	कामको विवरण	इकाई		आईटम दर (ठेक्काबाट)	आईटम दर (उपभोक्त गबाट)	८१/८ २ (ठेक्काबा ट)
१३२	१३३/१२- १ क	१२.५ मी.मी. बाक्लो सिमेन्ट बालुवा प्लाष्टर (१:३) भागमा सिलिङ्गमा गर्ने ।	व.मी.	रु.	517.91	460.92	
१३३	१३४/१२ -१ ख	१२.५ मी.मी. बाक्लो सिमेन्ट बालुवा प्लाष्टर (१:४) भागमा सिलिङ्गमा गर्ने ।	व.मी.	रु.	507.39	450.30	
१३४	१३५/१२ -१ ग	१२.५ मी.मी. बाक्लो सिमेन्ट बालुवा (१:४) मा सिलिङ्ग वाहेक अन्यत्र प्लाष्टर गर्ने ।	व.मी.	रु.	426.02	379.55	
१३५	१३७/१२ -१ घ	१२.५ मी.मी. बाक्लो सिमेन्ट बालुवा (१:६) मा काम गर्ने ।	व.मी.	रु.	404.22	357.95	
१३६	१४०/१२ -४ क	२० मी.मी. बाक्लो सिमेन्ट बालुवा प्लाष्टर (१:३) भागमा काम गर्ने ।	व.मी.	रु.	553.49	497.52	
१३७	१४१/१२ -४ ख	२० मी.मी. बाक्लो सिमेन्ट बालुवा प्लाष्टर (१:४) भागमा ।	व.मी.	रु.	534.52	478.48	
१३८	१४२/१२ -४ ग	२० मी.मी. बाक्लो सिमेन्ट बालुवा प्लाष्टर (१:६) भागमा ।	व.मी.	रु.	500.71	445.03	
कार्य समूह 'ट' :- रंग रोगनको काम							
१३९	१४५/१ ५४- १२-१ग	एक कोट सिमेन्ट प्राइमर सहित एक कोट लाइम पनिङ गर्ने काम	व.मी.	रु.	385.85	341.37	

खण्ड ०८, संख्या ०४, मकवानपुर, श्रावण ३० गते, २०८१ साल

सिभिल (जेनरल/भवन निर्माण सम्बन्धि) कार्यको आईटम दर रेट सारांश-२०८१/०८२

सि.नं.	आईटम नं.	कामको विवरण	इकाई		आईटम दर (ठेक्काबाट)	आईटम दर (उपभोक्त गबाट)	८१/८ २ (ठेक्काबा ट)
१४०	१४६/१ ३-१ ख	नयाँ सर्फेसमा हवाईटवास दुईकोट गर्ने काम (सिलिंगमा)	व.मी.	रु.	49.89	44.56	
१४१	१३-१ ख	नयाँ सर्फेसमा हवाईटवास दुईकोट गर्ने काम (अन्यत्र)	व.मी.	रु.	41.99	37.69	
१४२	१३-१ ग	नयाँ सिलिङ्ग सर्फेसमा हवाईटवास तीनकोट गर्ने काम ।	व.मी.	रु.	100.36	88.99	
१४३	१३-१ ग	नयाँ सर्फेसमा हवाईटवास तीनकोट गर्ने काम ।	व.मी.	रु.	83.36	74.20	
१४४	१३-२	पुरानो सर्फेसमा हवाईटवास गर्ने काम ।	व.मी.	रु.	22.72	20.29	
१४५	१३-३ क,ख	डिस्टेम्पर लगाउने काम एक कोट ।	व.मी.	रु.	146.09	132.81	
१४६	१३- ३क,ख,ग	डिस्टेम्पर लगाउने काम दुई कोट ।	व.मी.	रु.	204.02	184.90	
१४७	१३-४ क	वाटर प्रूफ सिमेन्ट पेन्ट एक कोट लगाउने काम ।	व.मी.	रु.	78.32	72.39	
१४८	१३-४ ख	वाटर प्रूफ सिमेन्ट पेन्ट दुई कोट लगाउने काम ।	व.मी.	रु.	180.09	163.53	
१४९	१३- ५क,ख	तयारी इनामेल पेन्ट एक कोट लगाउने । (एक कोट प्राइमर सहित)	व.मी.	रु.	239.55	217.34	

खण्ड ०८, संख्या ०४, मकवानपुर, श्रावण ३० गते, २०८१ साल

सिभिल (जेनरल/भवन निर्माण सम्बन्धि) कार्यको आईटम दर रेट सारांश-२०८१/०८२

सि.नं.	आईटम नं.	कामको विवरण	इकाई		आईटम दर (ठेक्काबाट)	आईटम दर (उपभोक्त गबाट)	८१/८ २ (ठेक्काबा ट)
१५०	१३- ५क,ख,ग	तयारी इनामेल पेन्ट दुई कोट लगाउने ।(एक कोट प्राईमर सहित)	व.मी.	रु.	368.69	334.64	
१५१	१३- ५क,ख,ग	तयारी इनामेल पेन्ट अस्तर विना दुई कोट लगाउने ।	व.मी.	रु.	345.69	312.04	
१५२	१३- ५क,ख	तयारी प्लाष्टिक इमल्सन पेन्ट एक कोट लगाउने । (एक कोट अस्तर सहित)	व.मी.	रु.	245.24	222.93	
१५३	१३- ५क,ख,ग	तयारी वेदरगार्ड पेन्ट दुई कोट लगाउने । (एक कोट अस्तर सहित)	व.मी.	रु.	469.89	434.08	
१५४	१३- ५क,ख,ग	तयारी प्लाष्टिक इमल्सन पेन्ट दुई कोट लगाउने । (एक कोट अस्तर सहित)	व.मी.	रु.	378.81	344.59	
१५५	१३-६	एक कोट अस्तर गरी दुई कोट तयारी एल्यूमीनियम पेन्ट गर्ने ।	व.मी.	रु.	373.04	337.70	
१५६	१३-७	एक कोट अस्तर लगाई दुई कोट रेड अक्साईड लगाउने काम ।	व.मी.	रु.	396.00	355.36	
१५७	१३-८ क	डबल बोर्डलड लिन्सिड आयल एक कोट लगाउने ।	व.मी.	रु.	59.91	53.50	

खण्ड ०८, संख्या ०४, मकवानपुर, श्रावण ३० गते, २०८१ साल

सिभिल (जेनरल/भवन निर्माण सम्बन्धि) कार्यको आईटम दर रेट सारांश-२०८१/०८२

सि.नं.	आईटम नं.	कामको विवरण	इकाई		आईटम दर (ठेक्काबाट)	आईटम दर (उपभोक्त गबाट)	८१/८ २ (ठेक्काबा ट)
१५८	१३-८ ख	डबल बोर्डलड लिन्सिड आयल दुई कोट लगाउने ।	व.मी.	रु.	117.76	104.97	
१५९	१३-९ क	स्थानीय कमर्सियल बार्नेस एक कोट लगाउने काम ।	व.मी.	रु.	94.51	85.96	
१६०	१३-९ ख	स्थानीय कमर्सियल बार्नेस दुई कोट लगाउने काम ।	व.मी.	रु.	183.47	166.46	
१६१	१३-१० क	अलकत्रा पेन्ट एक कोट लगाउने काम ।	व.मी.	रु.	53.73	49.34	
१६२	१३-१० ख	अलकत्रा पेन्ट दुई कोट लगाउने काम ।	व.मी.	रु.	93.86	86.09	
१६३	१३-११	चप्रा पालिश तीन कोट लगाउने काम ।	व.मी.	रु.	227.97	202.88	
१६४	१२-४ ग	टाटा रेड अक्साइड पेन्ट एक कोट लगाउने काम ।	व.मी.	रु.	173.19	165.62	
१६५	१२-४ घ	टाटा रेड अक्साइड पेन्ट दुई कोट लगाउने काम ।	व.मी.	रु.	333.47	314.24	
१६६		वाहिरी भागमा एककोट चुना पोत्ने काम ।	व.मी.	रु.	75.34	66.05	
१६७		वाहिरी भागमा एककोट रामतिलकले पोत्ने काम ।	व.मी.	रु.	123.64	113.51	
१६८	१३- ५ ख	अस्तर वाहेक एककोट तयारी इनामेल पेन्ट गर्ने काम ।	व.मी.	रु.	145.30	132.78	

खण्ड ०८, संख्या ०४, मकवानपुर, श्रावण ३० गते, २०८१ साल

सिभिल (जेनरल/भवन निर्माण सम्बन्धि) कार्यको आइटम दर रेट सारांश-२०८१/०८२

सि.नं.	आइटम नं.	कामको विवरण	इकाई		आइटम दर (ठेक्काबाट)	आइटम दर (उपभोक्त गबाट)	८१/८ २ (ठेक्काबा ट)
१६९	१३-५ ख,ग	अस्तर वाहेक दुईकोट तयारी इनामेल पेन्ट गर्ने काम ।	व.मी.	रु.	274.44	250.09	
१७०	१३-५ ख	अस्तर वाहेक एक कोट प्लाष्टिक इमल्सन पेन्ट गर्ने काम ।	व.मी.	रु.	150.99	138.37	
१७१	१३-५ ख,ग	अस्तर वाहेक दुई कोट प्लाष्टिक इमल्सन पेन्ट गर्ने काम ।	व.मी.	रु.	284.56	260.03	
१७२	१३-६	अस्तर वाहेक एक कोट आल्मुनियम पेन्ट गर्ने काम ।	व.मी.	रु.	130.05	117.73	
१७३	१३-६	अस्तर वाहेक दुई कोट आल्मुनियम पेन्ट गर्ने काम ।	व.मी.	रु.	265.94	240.51	
१७४	१३-७	अस्तर वाहेक एक कोट रेड अक्साइड पेन्ट गर्ने काम ।	व.मी.	रु.	132.73	119.17	
१७५	१३-७	अस्तर वाहेक दुई कोट रेड अक्साइड पेन्ट गर्ने काम ।	व.मी.	रु.	265.38	238.27	
कार्य समूह 'ठ' :- टिप्कार गर्ने काम							
१७६	१८२/१ ४-१ क	ईटाको गारोमा सिमेन्ट बालुवा (१:१) मा फ्लस टिप्कार गर्ने काम ।	व.मी.	रु.	314.80	279.08	
१७७	१४-१ क	ईटाको गारोमा सिमेन्ट बालुवा (१:१) मा रुल्ड टिप्कार गर्ने काम ।	व.मी.	रु.	447.07	394.09	

खण्ड ०८, संख्या ०४, मकवानपुर, श्रावण ३० गते, २०८१ साल

सिभिल (जेनरल/भवन निर्माण सम्बन्धि) कार्यको आईटम दर रेट सारांश-२०८१/०८२

सि.नं.	आईटम नं.	कामको विवरण	इकाई		आईटम दर (ठेक्काबाट)	आईटम दर (उपभोक्त गबाट)	८१/८ २ (ठेक्काबा ट)
१७८	१४-१ ख	ईटाको गारोमा सिमेन्ट बालुवा (१:२) मा फलस टिप्कार गर्ने काम ।	व.मी.	रु.	299.92	264.35	
१७९	१४-१ ख	ईटाको गारोमा सिमेन्ट बालुवा (१:२) मा रुल्ड टिप्कार गर्ने काम ।	व.मी.	रु.	432.19	379.36	
१८०	१४-१ ग	ईटाको गारोमा सिमेन्ट बालुवा (१:३) मा फलस टिप्कार गर्ने काम ।	व.मी.	रु.	292.11	256.63	
१८१	१४-१ ग	ईटाको गारोमा सिमेन्ट बालुवा (१:३) मा रुल्ड टिप्कार गर्ने काम ।	व.मी.	रु.	424.38	371.64	
१८२	१४-२ क	बोल्डर ढुंगाको गारोमा फलस रुल्ड टिप्कार गर्ने काम । (सि.बा.(१:१) मा)	व.मी.	रु.	375.38	336.76	
१८३	१४-२ ख	बोल्डर ढुंगाको गारोमा सिमेन्ट बालुवा (१:२) मा फलस रुल्ड टिप्कार गर्ने काम ।	व.मी.	रु.	346.81	308.47	
१८४	१४-२ ख	बोल्डर ढुंगाको गारोमा सिमेन्ट बालुवा (१:३) मा फलस रुल्ड टिप्कार गर्ने काम ।	व.मी.	रु.	332.39	294.21	
१८५	१४-३	एश्लर काममा फलस रुल्ड टिप्कार सिमेन्ट बालुवा (१:३) कार्य ।	व.मी.	रु.	229.42	201.35	
१८६	१४-४	४५ से.मी. X ४५ से.मी. चेप्टो ढुंगा छापेकोमा (१:३)	व.मी.	रु.	125.43	109.77	

खण्ड ०८, संख्या ०४, मकवानपुर, श्रावण ३० गते, २०८१ साल

सिभिल (जेनरल/भवन निर्माण सम्बन्धि) कार्यको आईटम दर रेट सारांश-२०८१/०८२

सि.नं.	आईटम नं.	कामको विवरण	इकाई		आईटम दर (ठेक्काबाट)	आईटम दर (उपभोक्त गबाट)	८१/८ २ (ठेक्काबा ट)
		सिमेन्ट बालुवाको टिप्कार ।					
१८७	१४-५	तेलिया ईटा छापेकोमा सिमेन्ट बालुवा (१:१) टिप्कार ।	व.मी.	रु.	261.28	229.73	
१८८	१४-६	३ मी.मी. फ्लसिंग प्लाष्टर सिमेन्ट बालुवा (१:१) मा लगाउने ।	व.मी.	रु.	290.88	258.61	
१८९	१४-७	चुनामा ३ मी.मी. फ्लसिंग प्लाष्टर लगाउने काम ।	व.मी.	रु.	320.27	287.86	
१९०	१४-८	सिमेन्टमा ३ मी.मी. बाक्लो फ्लसिंग प्लाष्टर लगाउने काम ।	व.मी.	रु.	314.91	282.59	
कार्य समूह 'ड' :- वाटर प्रुफिंग गर्ने काम							
१९१	१९७/१ ८-७	२ से.मी. मोटाईको सिमेन्ट बालुवा १:२ भागमा वाटर प्रुफ कम्पाउण्ड मिसाई डेम्प प्रुफिङ गर्ने ।	व.मी.	रु.	518.50	485.97	
१९२	१८-८	२.५ से.मी. मोटाई सिमेन्ट कंक्रीट (१:१½:३) डेम्प प्रुफीङ्ग गर्ने ।	व.मी.	रु.	580.64	534.07	
१९३	१८-९	३.८ से.मी. मोटाई सिमेन्ट कंक्रीट (१:२:४) डेम्प प्रुफीङ्ग गर्ने ।	व.मी.	रु.	717.66	657.44	

खण्ड ०८, संख्या ०४, मकवानपुर, श्रावण ३० गते, २०८१ साल

सिभिल (जेनरल/भवन निर्माण सम्बन्धि) कार्यको आइटम दर रेट सारांश-२०८१/०८२

सि.नं.	आइटम नं.	कामको विवरण	इकाई		आइटम दर (ठेक्काबाट)	आइटम दर (उपभोक्त गबाट)	८१/८ २ (ठेक्काबा ट)
१९४	१८-१०	एक कोट विटुमिन पेन्ट डेम्प प्रूफ कोर्समा लगाई बालुवाले छोप्ने ।	व.मी.	रु.	456.78	434.25	
१९५	१८-११	५०० गेजको पोलिथिन शीट एक तह विछ्याउने ।	व.मी.	रु.	173.80	154.67	
१९६	१८-१२ क	एक तह टारफेल्ड लगाउने काम ।	व.मी.	रु.	1270.80	1172.0 6	
१९७	१८-१२ ख	दुई तह टारफेल्ड लगाउने काम ।	व.मी.	रु.	2018.30	1870.5 5	
१९८	१८-१३ क	डेम्प प्रूफ ग्रेड टारफेल्ड एक तह लगाउने ।	व.मी.	रु.	1618.02	1481.4 0	
कार्य समूह 'ढ' :- मर्मत सम्बन्धी काम							
१९९	२०७/५- ३	गारोको मोहडामा विग्रेको ईटा निकाली सिमेन्ट बालुवा (१:६) मा गारो मर्मत गर्ने काम ।	घ.मी.	रु.	23625.43	21806. 93	
२००	२०८/५ -५	पुरानो सतहमा लिन्सीड आयलले पुछी तयारी इनामेल पेन्ट १ कोट लगाउने काम ।	व.मी.	रु.	240.98	222.35	
२०१	२०९/१ ९-५	सिमेन्ट वा वज्र प्लाष्टर भत्काई त्यसबाट आएको धुलो १० मी.पर हटाउने काम ।	व.मी.	रु.	109.30	95.04	

खण्ड ०८, संख्या ०४, मकवानपुर, श्रावण ३० गते, २०८१ साल

सिभिल (जेनरल/भवन निर्माण सम्बन्धि) कार्यको आईटम दर रेट सारांश-२०८१/०८२

सि.नं.	आईटम नं.	कामको विवरण	इकाई		आईटम दर (ठेक्काबाट)	आईटम दर (उपभोक्त गबाट)	८१/८ २ (ठेक्काबा ट)
२०२	२१०/१ ९-६	टाइल छाना भत्काई त्यसबाट भएको टाइल काठ आदि १० मी. पर सार्न लगाई राम्ररी थन्काउने काम ।	व.मी.	रु.	155.56	135.27	
२०३	२११/१ ९-१	माटोमा जोडेको गारो भत्काई त्यसबाट आएको सामग्री १० मी.सम्म हटाउने काम ।	घ.मी.	रु.	1072.72	932.80	
२०४	२१२/१ ९-२	सिमेन्ट वा वज्रमा जोडेको गारो भत्काई त्यसबाट आएको सामग्री १० मी. हटाउने काम ।	घ.मी.	रु.	2145.44	1865.6 0	
२०५	२१३/१ ९-३	आर.सि.सि. वा आर.वि.सि. काम भत्काई त्यसबाट आएको सामग्री १० मी. पर हटाउने काम ।	घ.मी.	रु.	11132.00	9680.0 0	
२०६	२१४/१ ९-४	प्लेन सिमेन्ट कंक्रीट वा वज्र कंक्रीट भत्काई त्यसबाट आएको सामग्री १० मी. पर हटाउने ।	घ.मी.	रु.	4048.00	3520.0 0	
२०७	२१५	पुरानो मार्बल फ्लोर तथा भित्तामा ज्यामीद्वारा मार्बल सतह अकजालिक	व.मी.	रु.	362.25	315.00	

खण्ड ०८, संख्या ०४, मकवानपुर, श्रावण ३० गते, २०८१ साल

सिभिल (जेनरल/भवन निर्माण सम्बन्धि) कार्यको आईटम दर रेट सारांश-२०८१/०८२

सि.नं.	आईटम नं.	कामको विवरण	इकाई		आईटम दर (ठेक्काबाट)	आईटम दर (उपभोक्त गबाट)	८१/८ २ (ठेक्काबा ट)
		एसिड हाली घोट्ने, सफा गर्ने कार्य ।					
२०८	२१७	पुरानो मोजायक फ्लोरिङ गरेको ठाउँमा घोटी सफा गरी मैन पालिस समेत गर्ने कार्य ।	व.मी.	रु.	383.28	338.00	
२०९	२१८	१" X ३/४" पानी पट्टी (१:३) सिमेन्ट मसलामा बनाई) बनाउने कार्य ।	र.मी.	रु.	473.82	414.13	
२१०	२१९	जस्तापाताको छाना भत्काई त्यसबाट निस्केका काठ तथा फलामे निर्माण सामग्रीहरु १० मी. पर लगाइ मिलाई थाक लगाउने कार्य ।	व.मी.	रु.	77.27	67.19	
२११	२२०	१" बाक्लो रुफिङ्ग टायल बुझा प्लाष्टर सिमेन्ट मसला (१:४) तयार गरी लगाउने कार्य ।	व.मी.	रु.	4201.09	3665.5 0	
२१२	२२१	मेसिनमेड क्ले टायल १:४ सिमेन्ट बालुवामा वाल सर्फसमा टांस्ने कार्य	व.मी.	रु.	4244.35	3916.4 2	
कार्य समूह 'ण' :- फलामको काम							

खण्ड ०८, संख्या ०४, मकवानपुर, श्रावण ३० गते, २०८१ साल

सिभिल (जेनरल/भवन निर्माण सम्बन्धि) कार्यको आईटम दर रेट सारांश-२०८१/०८२

सि.नं.	आईटम नं.	कामको विवरण	इकाई		आईटम दर (ठेक्काबाट)	आईटम दर (उपभोक्त गबाट)	८१/८ २ (ठेक्काबा ट)
२१३	४९/७ -५	आर.सी.सी. लागि फलामे डण्डी काट्ने, मोड्ने नक्सा अनुसार ठाउँमा राखी बाँध्ने काम	के.जी.	रु.	148.32	142.52	
२१४	२२२/२४ -१क	३ X २० मी.मी. फलामे ग्रिल बनाई खाक्सी लगाई एलुमिनियम पेन्ट समेत गरी जोड्ने	व.मी.	रु.	2415.00	2373.0 0	
२१५	२२३/२ ४-१ख	५ X २० मी.मी. फलामे ग्रिल बनाई खाक्सी लगाई एलुमिनियम पेन्ट समेत गरी जोड्ने	व.मी.	रु.	5635.00	5537.0 0	
२१६	२२४/ २४-४	फलामे कोलाप्सीबल गेट पेन्टिङ्ग र जडान समेत गर्ने (४" ग्यापमा)।	व.मी.	रु.	6440.00	6328.0 0	
२१७	२२५/२ ४-२	फलामे रोलिङ्ग सटर बनाई जडान गर्ने र पेन्टीङ्ग र ज्याला समेत ।	व.मी.	रु.	583.62	573.47	
२१८	२२६/२ ४-३	कम्पाउण्ड फलामे गेट बनाई जोड्ने पेन्टिङ्ग र ज्याला समेत ।	व.मी.	रु.	6641.25	6525.7 5	
२१९	२२७/२ ४-६	जि.आई.काढेतार (वार वेड वायर) लगाउने काम (१२ -१४ गेजको)।	र.मी.	रु.	93.50	84.06	

खण्ड ०८, संख्या ०४, मकवानपुर, श्रावण ३० गते, २०८१ साल

सिभिल (जेनरल/भवन निर्माण सम्बन्धि) कार्यको आईटम दर रेट सारांश-२०८१/०८२

सि.नं.	आईटम नं.	कामको विवरण	इकाई		आईटम दर (ठेक्काबाट)	आईटम दर (उपभोक्त गबाट)	८१/८ २ (ठेक्काबा ट)
२२०	२२८/२ ४-७	३ मिटर दूरीमा खम्बा गाडि ५ तह तथा २ वटा डायगोनल काढेतार लगाउने काम । ७५ मी.मी. X १०० मी.मी. X २.१ मी. लामो सालकाठको खम्बा प्रयोग गर्ने ।	र.मी.	रु.	1538.11	1357.5 8	
२२१	२२९/२ ४-७	३ मिटर दूरीमा खम्बा गाडि ५ तह तथा २ वटा डायगोनल काढेतार लगाउने काम । ७५ मी.मी. X १०० मी.मी. X २.१ मी. लामो कुकाठको खम्बा प्रयोग गर्ने ।	र.मी.	रु.	658.45	592.66	
२२२	२३०	कालो फलामे पाईपको ट्रस बनाई प्राइमर पेन्ट सहित साइटमा निर्देशानुसार जडान गर्ने काम ।	के.जी.	रु.	262.09	242.03	
२२३	२३१	कालो फलामे पाईपको पलिङ्ग बनाई प्राइमर पेन्ट सहित जडान गर्ने काम ।	व.मी.	रु.	212.83	198.83	
२२४	२३२	शिशौ काठको ३" X ४" साईजको हयाण्डरेल बनाई फिटिङ्ग गर्ने काम ।	व.मी.	रु.	2070.00	1800.0 0	

खण्ड ०८, संख्या ०४, मकवानपुर, श्रावण ३० गते, २०८१ साल

सिभिल (जेनरल/भवन निर्माण सम्बन्धि) कार्यको आइटम दर रेट सारांश-२०८१/०८२

सि.नं.	आइटम नं.	कामको विवरण	इकाई		आइटम दर (ठेक्काबाट)	आइटम दर (उपभोक्त गबाट)	८१/८ २ (ठेक्काबा ट)
२२५	२३३	३/४" X ३/४" साईजको स्क्वायर पाईपबाट २'-६" देखि ३'-०" सम्म उचाई भएको रेलिङ्ग बनाई ३"X४" साईजको साल वा शिशौको ह्याण्डरेल बनाई प्राइमर पेन्ट सहित जडान गर्ने काम ।	व.मी.	रु.	2070.00	2034.00	
२२६	२३४	३/४" X ३/४" साईजको स्क्वायर पाईपबाट २'-६" देखि ३'-०" सम्म उचाई भएको रेलिङ्ग बनाई ११/२" व्यासको कालो पाईपको ह्याण्डरेल बनाई सप्लाई, जडान एवं प्राइमर पेन्ट सहित सम्पूर्ण काम ।	व.मी.	रु.	3105.00	3051.00	

खण्ड ०८, संख्या ०४, मकवानपुर, श्रावण ३० गते, २०८१ साल

सिभिल (जेनरल/भवन निर्माण सम्बन्धि) कार्यको आइटम दर रेट सारांश-२०८१/०८२

सि.नं.	आइटम नं.	कामको विवरण	इकाई		आइटम दर (ठेक्काबाट)	आइटम दर (उपभोक्त गबाट)	८१/८ २ (ठेक्काबा ट)
२२४	२३५	५० मी.मी. Ø को कालो फलामे पाईप पोष्ट २ मीटर दूरीमा २०X२०X४ मी.मी. र २५ X २५ X ४ मी.मी. साईजको फलामे एङ्गल फ्रेमको विचमा १० S.W.G.G. I. Chain Link २"X२" को मेस साइज जाली जडान गर्ने र ३ X २० को फलामे पाताको ग्रिल ०.१५ मी. अग्लो बनाई माथि जडान गरी फेब्रिकेशन गरी प्राइमर पेन्ट सहित सम्पूर्ण कार्य ।	व.मी.	रु.	3264.55	3042.7 4	
२२५	२३६	५० मी.मी. Ø को कालो फलामे पाईप पोष्ट २ मीटर दूरीमा २५ X २५ X ४ मी.मी. साईजको फलामे एङ्गल फ्रेममा ७ मी.मी. च फलामे डण्डीको डायगोनली जाली ६२ X ६२ मी.मी. साइजमा जडान गर्ने र ३X२० को फलामे पाताको	व.मी.	रु.	3223.96	3002.8 5	

खण्ड ०८, संख्या ०४, मकवानपुर, श्रावण ३० गते, २०८१ साल

सिभिल (जेनरल/भवन निर्माण सम्बन्धि) कार्यको आइटम दर रेट सारांश-२०८१/०८२

सि.नं.	आइटम नं.	कामको विवरण	इकाई		आइटम दर (ठेक्काबाट)	आइटम दर (उपभोक्त गबाट)	८१/८ २ (ठेक्काबा ट)
		ग्रिल ०.१५ मी. अग्लो बनाई माथि जडान गरी फेब्रिकेशन गरी प्राइमर पेन्ट सहित सम्पूर्ण कार्य ।					
२२६	२३७	विभिन्न साईजको फलामे एङ्गल फेब्रिकेशन गरी प्राइमर पेन्ट सहित गर्ने काम ।	व.मी.	रु.	212.00	198.01	
२२७	२३८	मालसामान उपलब्ध गरी १.२ मि.मि. फाईबर ग्लास (कोरोगेटेड) शीटले छाना छाउने काम ।	व.मी.	रु.	4349.79	4242.90	
२२८	२३९	मालसामान उपलब्ध गरी १.२ मि.मि. फाईबर ग्लास शीटको धुरी बनाई जडान गर्ने काम पुरा ।	र.मी.	रु.	1339.05	1250.63	
२२९	२४०	फलामे घुम्ने भन्याङ्ग : ४"-६' च सम्मको मध्यम श्रेणीको कालो पाईप पोष्ट प्रयोग गरी ३/४"ह३/४" को स्क्वायर पाईप मा ११/४"च को मध्यम श्रेणीको कालो पाईपको हयाण्डरेल प्रयोग गरी	र.मी.	रु.	9487.50	9322.50	

खण्ड ०८, संख्या ०४, मकवानपुर, श्रावण ३० गते, २०८१ साल

सिभिल (जेनरल/भवन निर्माण सम्बन्धि) कार्यको आइटम दर रेट सारांश-२०८१/०८२

सि.नं.	आइटम नं.	कामको विवरण	इकाई		आइटम दर (ठेक्काबाट)	आइटम दर (उपभोक्त गबाट)	८१/८ २ (ठेक्काबाट)
		२'-०" देखि २'-६" चौडाईसम्मको फलामे घुम्ने भ्याङ्ग आवश्यक सामग्रीहरु सहित					
कार्य समूह 'त' :- आलुमिनियम र फाइबर पार्टिसन तथा भ्याल ढोका,जिप्सम फ्ल्स सिलिङ्ग आदी							
	२४१	Aluminium Partition					
२३०	२४१.१	Supplying & fixing of Aluminium partation Nepal series(3820,3821)Single Partation(75.5*38.5)(63.3*38.1)---5 mm clear glass with all fittings	व.मी.	रु.	7486.27	7356.07	
२३१	२४१.२	Supplying & fixing of Aluminium partation Nepal series(3820,3821)Single Partation(75.5*38.5)(63.3*38.1)---8 mm clear glass with all fittings	व.मी.	रु.	9255.75	9094.78	
२३२	२४१.३	Supplying & fixing of Aluminium partation partation 100 series 10.16*44.5 *88.44.5---5	व.मी.	रु.	9936.32	9763.52	

खण्ड ०८, संख्या ०४, मकवानपुर, श्रावण ३० गते, २०८१ साल

सिभिल (जेनरल/भवन निर्माण सम्बन्धि) कार्यको आइटम दर रेट सारांश-२०८१/०८२

सि.नं.	आइटम नं.	कामको विवरण	इकाई		आइटम दर (ठेक्काबाट)	आइटम दर (उपभोक्त गबाट)	८१/८ २ (ठेक्काबा ट)
		mm clear lass with all fittings					
२३३	२४१.४	Supplying & fixing of Almunium partation partation 100 series 10.16* 44.5 *88.44.5---8 mm clear lass with all fittings	व.मी.	रु.	9862.08	9690.5 6	
	२४२	Aluminium Door					
२३४	२४२.१	Supplying & fixing of Aluminium 100 series Door 44.45*47.62/44.5*4 7.8)5mm clear glass with all fittings handle/ kabja/Brass/lock etc	व.मी.	रु.	9255.75	9094.7 8	
२३५	२४२.२	Supplying & fixing of Aluminium 78 series Door (64.5*32/29*63.5)5 mm clear glass with all fittings handle/ kabja/Brass/lock etc	व.मी.	रु.	9527.98	9362.2 8	
	२४३	Aluminium Sliding Window					
२३६	२४३.१	Supplying & fixing of Aluminium 100 series Sliding window Nepal serie(101.6*41.5)	व.मी.	रु.	12114.15	11903. 47	

खण्ड ०८, संख्या ०४, मकवानपुर, श्रावण ३० गते, २०८१ साल

सिभिल (जेनरल/भवन निर्माण सम्बन्धि) कार्यको आईटम दर रेट साराशः-२०८१/०८२

सि.नं.	आईटम नं.	कामको विवरण	इकाई		आईटम दर (ठेक्काबाट)	आईटम दर (उपभोक्त गबाट)	८१/८ २ (ठेक्काबा ट)
		5mm clear glass with fittings handle/ kabja/Brass/lock etc					
२३७	२४३.२	Supplying & fixing of Aluminium 78 series Sliding window Nepal serise(78*26) 5mm clear glass with fittings handle/ kabja/Brass/lock etc	व.मी.	रु.	10753.01	10566.00	
२३८	२४४	Aluminium Composite/Stp Pannel					
२३९	२४४.१	Supplying & fixing of Almunium Composite panell for extrior Application 4 mm Board	व.मी.	रु.	6669.59	6553.59	
२४०	२४४.२	Supplying & fixing of Almunium Composite panell for extrior Application 3 mm Board	व.मी.	रु.	5989.02	5884.86	
	२४५	Fibre					
२४१	२४५.१	फाइबरका तयारी भ्याल तथा ढोका (सादा) फिटिङ्ग समेत	व.मी.	रु.	9255.75	9094.78	

खण्ड ०८, संख्या ०४, मकवानपुर, श्रावण ३० गते, २०८१ साल

सिभिल (जेनरल/भवन निर्माण सम्बन्धि) कार्यको आइटम दर रेट सारांश-२०८१/०८२

सि.नं.	आइटम नं.	कामको विवरण	इकाई		आइटम दर (ठेक्काबाट)	आइटम दर (उपभोक्त गबाट)	८१/८ २ (ठेक्काबा ट)
२४२	२४५.२	फाइबरका तयारी भ्याल तथा ढोका (वुटे) फिटिङ्ग समेत	व.मी.	रु.	11978.03	11769.72	
२४३	२४६	False ceiling by Gypsum ,Gypsum Board : 12mm thickness including all necessary fittings and labour charges.	व.मी.	रु.	1856.10	1823.82	

आज्ञाले

देब चन्द्र गतौला

प्रमुख प्रशासकीय अधिकृत

राक्सिराङ्ग गाउँपालिका, चैनपुर, मकवानपुर/मुद्रण रु ५० मात्र ।